



Optimal Monetary Policy under Bounded Rationality¹

Jonathan Benchimol* and Lahcen Bounader**

Discussion Paper 2019.07

July 2019

Bank of Israel - <http://www.boi.org.il>

¹ The views expressed in this paper are those of the authors and do not necessarily represent the views of the Bank of Israel, the International Monetary Fund, its Executive Board, or IMF management. The authors thank Itai Agur, Olivier Blanchard, Jeffrey Campbell, Mátyás Farkas, Jorge Ivan Canales Kriljenko, Xavier Gabaix, Lars Peter Hansen, Ori Heffetz, Seppo Honkapohja, Doron Kliger, Subir Lall, Luca Onorante, Johannes Pfeifer, John Roberts, Guy Segal, Michel Strawczynski, participants at the 2nd CEPR MMCN Annual Conference at Stanford University, and participants at the Hebrew University of Jerusalem, the Bank of Israel, the Bank of Finland and the Bucharest University of Economic Studies research seminars for their useful comments.

* Bank of Israel, Jerusalem, Israel.

Email: jonathan.benchimol@boi.org.il

** International Monetary Fund, Washington, D.C., United States.

Email: lbounader@imf.org

**Any views expressed in the Discussion Paper Series are those of the authors
and do not necessarily reflect those of the Bank of Israel**

חטיבת המחקר, בנק ישראל ת"ד 780 ירושלים 91007
Research Department, Bank of Israel. POB 780, 91007 Jerusalem, Israel.

Optimal Monetary Policy under Bounded Rationality

Jonathan Benchimol and Lahcen Bounader

Abstract

We build a behavioral New Keynesian model that emphasizes different forms of myopia for households and firms. By examining the optimal monetary policy within this model, we find four main results. First, in a framework where myopia distorts agents' inflation expectations, the optimal monetary policy entails implementing inflation targeting. Second, price level targeting emerges as the optimal policy under output gap, revenue, or interest rate myopia. Given that bygones are not bygones under price level targeting, rational inflation expectations are a minimal condition for optimality in a behavioral world. Third, we show that there are no feasible instrument rules for implementing the optimal monetary policy, casting doubt on the ability of simple Taylor rules to assist in the setting of monetary policy. Fourth, bounded rationality may be associated with welfare gains.

מדיניות מוניטרית אופטימלית בתנאי רציונליות מוגבלת

יונתן בן שימול ולאהסן באונאדר

תקציר

במאמר זה בנינו מודל ניו-קיינסיאני התנהגותי, המבליט צורות שונות של קוצר ראות בהתנהגותם של משקי בית וחברות. בחינת המדיניות המוניטרית האופטימלית במסגרת מודל זה העלתה ארבע תוצאות עיקריות. ראשית, בהתחשב בקוצר הראות, המעוות את ציפיות האינפלציה, המדיניות האופטימלית כוללת הצבת יעד אינפלציה. שנית, מתברר שקביעת יעד של רמת המחירים היא המדיניות האופטימלית בהינתן קוצר הראות של משקי הבית והחברות ביחס לפער התוצר, להכנסות או לשיעור הריבית. בהינתן שבמסגרת של יעד מחירים העבר אינו נחלת העבר בלבד, ציפיות אינפלציה רציונליות הן תנאי מינימלי למדיניות אופטימלית בעולם של רציונליות מוגבלת. שלישית, מתברר שיישום כללים של מדיניות מוניטרית אופטימלית אינו אפשרי, מה שמעמיד בספק את יכולתם של כללי טיילור פשוטים לסייע בנייהול המדיניות המוניטרית. ורביעית, ייתכן שרציונליות מוגבלת דווקא מסייעת למדיניות להשיג יתרונות בתחום הרווחה.

1 Introduction

This paper investigates the dependence of optimal monetary policy on specific myopias¹ characterizing households and firms as well as their practical implications for monetary policy conduct. Behavioral monetary policy is an essential concept for central banks that once focused on managing gaps (e.g., inflation gap, output gap) as today’s monetary policy focuses on managing expectations. Economic agents collect prices in supermarkets or through the internet, but collecting values of the output gap is more complicated. Such illustrative heterogeneous myopia between prices (inflation) and quantities (output) concerns both central banks and researchers (e.g., the Phillips Curve). This relative distortion between prices and quantities influences monetary policy, justifying the analysis of the optimal monetary policy under heterogeneous myopia.

Our finding challenges existing conclusions about optimal monetary policy under rational expectations as well as under bounded rationality—including rational inattention and learning—in the literature. The policy conclusion from our behavioral framework shows that bounded rationality has essential implications for the conduct of monetary policy and emphasizes that both inflation targeting (IT) or price level targeting (PLT) could be (behaviorally) optimal under different circumstances and bounded rationality extensions. Previous literature has shown that the optimal policy resulting from the rational New Keynesian framework recommends a form of PLT, while rational inattention finds small differences in terms of welfare compared to the rational case, which do not alter the policy conclusions (Maćkowiak and Wiederholt, 2015). Learning models, as surveyed in Eusepi and Preston (2018), convey the conclusion that a form of PLT could be an adequate proxy for the optimal policy response. However, Gabaix (2019) finds that PLT is suboptimal with behavioral agents. We challenge these previous results by showing that PLT is optimal when assuming some forms of bounded rationality, particularly those not involving macroeconomic inattention to inflation, while it is suboptimal in other cases. Under PLT, *bygones are not bygones*, which requires awareness (rationality) from the public regarding inflation developments.

There is broad agreement that the rational expectations hypothesis falls short in capturing the complex dynamics between monetary policy decisions and agents’ anticipations. There is less agreement on the appropriate deviation from this hypothesis to investigate monetary policy questions. Overall, the optimal monetary policy conclusions from the rational inattention or learning literature are the same as in the rational model or, at best, deviate slightly without altering how monetary

¹The terms myopia, inattention, and bounded rationality are used interchangeably in this paper.

policy should be conducted. Our paper contributes to this debate.

Optimal monetary policy is widely analyzed in the literature through New Keynesian models (Clarida et al., 1999; Woodford, 2003), which emphasize that agents' expectations about the future are rational and somehow perfect. According to Blanchard (2009, 2018), this assumption is exaggerated and quite far from reality, even when considering aggregated representative agents. Who knows what the inflation rate will be next month? What will the output gap be next quarter? Who looks at every macroeconomic variable when deciding about consumption? Even perfectly informed people do not act this way. Despite this caveat, academics and practitioners consider this model to be the workhorse of monetary policy analysis, and its conclusions still shape the monetary economics literature.²

In this paper, we extend the New Keynesian model to account for agents' inattentiveness to macroeconomic variables. Since agents' expectations are bounded (Andrade and Le Bihan, 2013; Coibion and Gorodnichenko, 2015; Gennaioli et al., 2016), we relax the rationality assumption in favor of bounded rationality, whereby agents are assumed to be partially myopic and unable to perfectly anticipate macroeconomic developments (Akerlof and Yellen, 1987). Bringing non-rational elements into New Keynesian models to highlight their impact on optimal monetary policy prescriptions is essential for policymakers. Our model provides policymakers with a set of policies and a realistic tool to communicate their policies to real (non-rational) economic agents. The bounded rationality of households and firms leads policymakers to question the optimality of monetary policy under such forms of inattention.³

Inspired by the bounded rationality approach of Gabaix (2019) but departing from his model and calibration, we derive optimal monetary policy results under differentiated forms of myopia that complement the latter.⁴ While the transition from subjective to objective expectations we use is realistic, the general production function we use for the representative firm lead to substantial differences in the trade-off between output and inflation, changing the amplitude of the central bank's reaction to cost-push shocks.⁵ Our study of optimal monetary policy is conducted through a

²As Stiglitz (2011) notes, one crucial underlying assumption of the traditional models is a rational behavior of the economy; however, the real-world economy seems inconsistent with any model of rationality.

³Our framework assumes that the central bank behaves rationally. By optimizing behavioral agents, a behavioral central bank is not necessary for our research question.

⁴Here, bounded rationality means an agent's myopia to variables of interest in its decision-making. The plausibility of this approach finds its roots in the work of Kahneman (1973), who attributes attention to effort and inattention, by deduction, to laziness. Consequently, it is more convenient to model *Homo sapiens* as myopic agents. The key novelty of this paper, that agents can be myopic about specific economic variables, is discussed in Section 3.1.

⁵While our qualitative results do not hinge on this assumption, it modifies the amplitude of the interest rate responses to shocks.

welfare-relevant behavioral New Keynesian model,⁶ which allows a model-consistent welfare criterion. Optimal monetary policy in a fully microfounded behavioral New Keynesian dynamic stochastic general equilibrium framework, using a second-order approximation of the household’s utility, is assessed. The first- and second-best equilibria under commitment and discretion, respectively, are examined. The possibility that an optimal simple rule implements the first best solution is analyzed. All these configurations are explored through variants of the behavioral New Keynesian model emphasizing the output gap, interest rate, inflation, revenue, general or full myopia.

This paper is related to several strands of the literature. First, it extends the monetary economics literature (Clarida et al., 1999; Woodford, 2003; Galí, 2015) by relaxing the rational expectation hypothesis. Second, compared to the learning (Evans and Honkapohja, 2012, 2013; Woodford, 2013) or the rational inattention (Sims, 2003; Maćkowiak and Wiederholt, 2009, 2015) literature, it provides an alternative way to deviate from the rational expectation hypothesis while providing richer policy conclusions. Third, based on Gabaix (2014), it extends the optimal monetary policy literature.

On the practical side, we find that simple instrument rules, such as Taylor (1993), its variations, price level or nominal GDP (NGDP) rules, are unable to implement the optimal policy path. This result calls for the adoption of targeting rules in the sense of Woodford (2003, 2010) as a practical guideline for optimal monetary policy conduct. Such a proposal was made long ago by Svensson (2003). Our result can be seen as a formal proof of the shortsightedness of mechanical simple rules in the policymaking process, especially in a behavioral world.

Additionally, we find that bounded rationality is not necessarily associated with decreased welfare. Several forms of economic inattention, especially extreme ones, can increase welfare. By contrast, output gap myopia implies significant welfare losses compared to the rational case. The appropriate response from the central bank to economic disturbances improves the social welfare of behavioral agents.

The remainder of the paper is organized as follows. Section 2 describes the behavioral New Keynesian model, and Section 3 outlines the methodology used for the study of optimal monetary policy. Section 4 and Section 5 present the optimal monetary policy under commitment and discretion, respectively. Section 6 characterizes optimal simple rules and weights within the same model. Section 7 interprets and discusses our findings to draw some policy implications in Section 8. Section 9 presents the concluding remarks, and Section 10 presents our derivations and robustness checks.

⁶Normative analysis with exogenous myopia parameters is made possible by relying on the *local rigidity* property explained in Section 3.1.

2 The model

Our model is based on the psychological foundations of bounded rationality brought by Gabaix (2014, 2019), among others (De Grauwe, 2012; Evans and Honkapohja, 2013; Woodford, 2013), to macroeconomic analysis. In this framework, agents' representations of the economy are sparse, i.e., when they optimize, agents care only about a few variables that they observe with some myopia.

Departing from Gabaix (2019), our model assumes decreasing returns to scale and different types of myopia other than general myopia. This framework will serve later on to assess optimal monetary policy under different policy designs: discretion, commitment, and optimal simple rules.

2.1 Households

The infinitely lived rational representative household's utility is

$$U(c_t, N_t) = \frac{c_t^{1-\gamma} - 1}{1-\gamma} - \frac{N_t^{1+\phi}}{1+\phi} \quad (1)$$

where c_t is real consumption and N_t is labor supply. γ is the coefficient of the household's relative risk aversion, i.e., the inverse of the intertemporal elasticity of substitution, and ϕ is the inverse of the Frisch elasticity of labor supply, i.e., the inverse of the elasticity of work effort with respect to the real wage.

The household maximizes

$$\mathbb{E}_0 \sum_{t=0}^{\infty} \beta^t U(c_t, N_t) \quad (2)$$

where \mathbb{E} is the usual expectation operator and β is the static discount factor subject to the wealth dynamics

$$k_{t+1} = (1 + r_t)(k_t - c_t + y_t) \quad (3)$$

and the real income as

$$y_t = w_t N_t + y_t^f \quad (4)$$

where k_t is the household's wealth, r_t the real interest rate, y_t the agent's real income, w_t the real hourly wage, N_t the worked hours, and y_t^f the profit income.

The rational household's problem is to maximize its period utility (Eq. 2) subject to its wealth evolution (Eq. 3).

The behavioral household maximizes the same lifetime utility (Eq. 2) but does not pay full attention to all variables in the budget constraints, as correctly process-

ing information entails a cost. The behavioral agent perceives reality with some myopia, which is associated with this information cost.

Let $\hat{r}_t = r_t - \bar{r}$ and $\hat{y}_t = y_t - \bar{y}$ be the deviations of real interest rate and output, respectively, from their steady state. Following Gabaix (2019), the behavioral agent's inattention is associated with *perceived* deviations from the steady-state real interest rate, $\hat{r}_t^{BR} = \hat{r}^{BR}(S_t)$, the function of the current state vector of the economy S_t , and real income, $\hat{y}_t^{BR} = \hat{y}^{BR}(N_t, S_t)$.

The behavioral agent's budget constraint becomes

$$k_{t+1} = (1 + \bar{r} + \hat{r}^{BR}(S_t)) (k_t - c_t + \bar{y} + \hat{y}^{BR}(N_t, S_t)) \quad (5)$$

where $\hat{r}^{BR}(S_t) = m_r \hat{r}_t(S_t)$ and $\hat{y}^{BR}(N_t, S_t) = \hat{y}^{BR}(S_t) + w_t(N_t - N(S_t))$.

$\hat{y}^{BR}(N_t, S_t)$ is the perceived personal income while $\hat{y}^{BR}(S_t) = m_y \hat{y}_t(S_t)$ is the aggregate income. The equation of the perceived income indicates that the behavioral agent perceives only a fraction of the aggregate income but perfectly perceives his marginal income.

Note that m_r and m_y are myopia parameters⁷ in $[0, 1]$. For $m_r = m_y = 1$, the rational household's budget constraint is recovered. Separately, m_r is the real interest rate myopia, and m_y is the real income myopia.

The future state vector of the whole economy populated by rational agents evolves as

$$S_{t+1} = f(S_t, \epsilon_{t+1}) \quad (6)$$

where f is a function of the current state vector of the economy⁸ and an innovation process vector in the next period, ϵ_{t+1} .

The future state vector of the whole economy populated by behavioral agents evolves as

$$S_{t+1} = \bar{m} f(S_t, \epsilon_{t+1}) \quad (7)$$

where $\bar{m} \in [0, 1]$ represents the general myopia of the agent regarding the economy's state. When $\bar{m} = 1$, the rational agent's law of motion (Eq. 6) is recovered.

Consequently, the problem of the behavioral household consists of maximizing the period utility (Eq. 2) subject to the behavioral wealth (Eq. 5) and the behavioral state vector of the economy (Eq. 7).

By clearing the goods market, in which output is equated with consumption $y_t = c_t$, and solving the household's problem with respect to c_t , the behavioral IS

⁷See Section 3.1 for more details about these parameters.

⁸The function f may contain technological shocks, fiscal measures, etc.

equation⁹ becomes

$$\tilde{y}_t = M\mathbb{E}_t[\tilde{y}_{t+1}] - \sigma(i_t - \mathbb{E}_t[\pi_{t+1}] - r_t^n) \quad (8)$$

where \tilde{y}_t is the output gap expressed as deviations of output from its natural level, i_t is the nominal interest which links to r_t by the Fisher equation, r_t^n is the natural level of the real interest rate, $M = \bar{m}/(R - m_Y\bar{r})$, $\sigma = m_r/(\gamma R(R - m_Y\bar{r}))$ where $m_Y = (\phi m_y + \gamma)/(\phi + \gamma)$ and $R = 1 + \bar{r} = 1/\beta$ and \bar{r} is the steady state of the real interest rate.

The First-Order Condition (FOC) with respect to N_t is

$$w_t = \gamma c_t + \phi n_t \quad (9)$$

where n_t is the log deviation of employment, N_t , from its steady state.

The rational IS curve obtained as a particular case, when $m_r = m_y = \bar{m} = 1$, is

$$\tilde{y}_t = \mathbb{E}_t[\tilde{y}_{t+1}] - \sigma_{re}(i_t - \mathbb{E}_t[\pi_{t+1}] - r_t^n) \quad (10)$$

where $\sigma_{re} = 1/(\gamma R)$.

By comparing the behavioral (Eq. 8) and the rational (Eq. 10) IS curves,¹⁰ the future output appears to have less influence on current output in the behavioral equation ($M < 1$). Moreover, the transmission of monetary policy to the real economy is stronger in the rational than in the behavioral case ($\sigma_{re} \geq \sigma$).

2.2 Firms

A continuum of firms populates our economy. Each firm i produces differentiated goods using the same technology described by

$$Y_t(i) = A_t N_t(i)^{1-\alpha} \quad (11)$$

where A_t is the technological factor (identical across all firms) that evolves such that $a_t = \rho_a a_{t-1} + \varepsilon_t^a$, where $a_t = \ln A_t$ and $\varepsilon_t^a \sim N(0; \sigma_a)$, *i.i.d.* over time, and $N_t(i)$ are the worked hours at firm i , which aggregates as $N_t = \int_0^1 N_t(i) di$.

Note that unlike Gabaix (2019), we assume decreasing returns to scale ($\alpha > 0$), allowing our inflation dynamics to depend on the elasticity of substitution between different goods, ε . Assuming constant returns to scale ($\alpha = 0$) in the production

⁹See Appendix A.1 for a detailed derivation of the IS curve (Eq. 8).

¹⁰To obtain the rational version of the IS equation (Eq. 10), the reader is invited to expand Eq. 41 in Appendix A.1, as we do for the behavioral case.

function removes the role of this elasticity of substitution in the Phillips curve.¹¹

Following Galí (2015), firms face Calvo (1983) pricing frictions and adjust their prices in each period with probability $1 - \theta$. The optimal price setting of the firm, P_t^* , is the price that maximizes the current market value of the profits generated while that price remains effective.

The problem of the behavioral firm is to maximize

$$\sum_{k=0}^{\infty} \theta^k \mathbb{E}_t^{BR} [\Lambda_{t,t+k} (P_t^* Y_{t+k|t} - \Psi_{t+k}(Y_{t+k|t}))] \quad (12)$$

subject to the sequence of demand constraints

$$Y_{t+k|t} = \left(\frac{P_t^*}{P_{t+k}} \right)^{-\varepsilon} Y_{t+k} \quad (13)$$

where behavioral agents have a subjective expectation¹² denoted by the operator $\mathbb{E}_t^{BR}[\cdot]$, $\Lambda_{t,t+k} = \beta^k (c_{t+k}/c_t)^{-\gamma} (P_{t+k}/P_t)$ is the stochastic discount factor in nominal terms, $\Psi_{t+k}(\cdot)$ is the cost function, $Y_{t+k|t}$ is the output in period $t+k$ for a firm that last reset its price in period t , P_t^* is the optimal price the behavioral firm seeks to determine and P_t is the price level of the overall economy.

Expanding the FOC of the firm's problem around the zero-inflation steady state¹³ yields

$$p_t^* - p_{t-1} = (1 - \beta\theta) \sum_{k \geq 0} (\beta\theta)^k \mathbb{E}_t^{BR} [\widehat{mc}_{t+k|t} + p_{t+k} - p_{t-1}] \quad (14)$$

where $\widehat{mc}_{t+k|t}$ is the deviation of the real marginal cost, $mc_{t+k|t} = \ln \frac{\Psi'_{t+k}(Y_{t+k|t})}{P_{t+k}}$, in $t+k$ of a firm that last reset its price at t from its steady state value $mc = -\ln \frac{\varepsilon}{\varepsilon-1}$.

The resulting behavioral Phillips curve is¹⁴

$$\pi_t = \beta M^f \mathbb{E}_t [\pi_{t+1}] + \kappa \tilde{y}_t \quad (15)$$

where $M^f = \theta \bar{m} / (1 - (1 - \theta) m_\pi^f)$ and $\kappa = \frac{(1-\theta)(1-\beta\theta)m_x^f}{1-(1-\theta)m_\pi^f} \Theta (\gamma + \frac{\phi+\alpha}{1-\alpha})$, in which $\Theta = (1 - \alpha) / (1 - \alpha + \alpha\varepsilon)$. m_x^f and m_π^f represent the perfect foresight fraction by the firm of the future marginal cost¹⁵ and inflation, respectively.

¹¹As presented below, this elasticity plays an essential role in the Phillips curve (Eq. 15). Decreasing return to scale also allows us to provide complete robustness checks (Appendix B.1).

¹²See Appendix A.1 for the definition of this subjective expectation operator.

¹³See Eq. 50 in Appendix A.2 for further details.

¹⁴See Appendix A.2 for detailed derivations.

¹⁵By extension, as it proportionally enters κ , we recall this marginal cost myopia an output gap myopia.

Assuming constant return to scale¹⁶ affects the core optimal monetary policy analysis, which depends on the trade-off between inflation and the output gap, κ . In our Phillips curve (Eq. 15), the coefficient κ depends on α , the decreasing return to scale parameter.

Interestingly, $\frac{\partial \kappa}{\partial \alpha} = m_x^f \Phi < 0$, where $\Phi = \frac{(1-\beta\theta)(1-\theta)(\phi+1-(\gamma+\phi)\epsilon)}{(\alpha\epsilon-\alpha+1)^2}$, i.e. κ is decreasing with α .

Another interesting observation about α concerns its relationship with the output gap weight in the microfounded loss function,¹⁷ w_x/w_π . As $\frac{\partial w_x/w_\pi}{\partial \alpha} = \frac{1}{\theta\epsilon}\Phi < 0$, w_x/w_π is a decreasing function of α . Consequently, the central bank gives less attention to the output gap objective when α increases.

The rational Phillips curve, obtained by assuming $m_x^f = m_\pi^f = \bar{m} = 1$, is

$$\pi_t = \beta \mathbb{E}_t [\pi_{t+1}] + \kappa_{re} \tilde{y}_t \quad (16)$$

where $\kappa_{re} = \frac{(1-\theta)(1-\beta\theta)}{\theta} \Theta \left(\gamma + \frac{\phi+\alpha}{1-\alpha} \right)$.

The first contrast between the behavioral (Eq. 15) and the rational (Eq. 16) Phillips curves is the weight of future inflation in the determination of current inflation. This weight is more attenuated in the behavioral than in the rational equation (as $M^f < 1$). Second, the sensitivity of inflation to the output gap in the rational model is greater than that in the behavioral model (as $\kappa_{re} > \kappa$).

Note that Gabaix (2019) derived a similar Phillips curve, at least in its functional form: inflation depends on its expectations as well as on the output gap. The only difference is related to the magnitude of the feedback from each variable to inflation. The feedback coefficients from Gabaix (2019) are as follows

$$M_G^f = \bar{m} \left(\theta + \frac{1-\beta\theta}{1-\beta\theta\bar{m}} m_\pi^f (1-\theta) \right) \quad (17)$$

$$\kappa_G = m_x^f \frac{(1-\theta)(1-\beta\theta)}{\theta} (\gamma + \phi) \quad (18)$$

Eq. 17 and Eq. 18 highlight two substantial differences.

First, the main difference between M^f (Eq. 15) and M_G^f consists of the use of the term structure of expectations. In our formulation, M^f , we use the term structure of expectation starting from Eq. 58, while Gabaix (2019) used the same formula starting from Eq. 57 in the Appendix A.2. Our formulation is consistent with the term structure of expectations stipulated in Lemma 2.6 in Gabaix (2019). Unlike the level of the variable, its deviation from the steady state should be the argument for the term structure of the expectations. This correct transition from subjective

¹⁶Or, in other words, $\alpha = 0$ in the production function (Eq. 11).

¹⁷The formal definitions of w_x and w_π are available in Section 3.3.

to objective expectations explains why the Phillips Curve in Gabaix (2019) is not nested in our formulation.

Second, the difference between κ (Eq. 15) and κ_G is related to our assumption of decreasing returns to scale in the production function. Gabaix (2019) assumes constant return to scale, $\alpha = 0$, which simplifies to κ_G . Although this assumption may seem irrelevant, we noticed that κ is a function of α in our formulation and, more importantly, that κ is decreasing with α ($\frac{\partial \kappa}{\partial \alpha} < 0$). In other words, the decreasing return to scale assumption might lengthen the feedback from real variables to nominal variables.

In addition to being more realistic, assuming a decreasing return to scale allows a role for inflation myopia (m_π^f) in κ that is nonexistent in κ_G . When κ is decreasing with α in the general case ($\alpha \neq 0$), the feedback from output to inflation is incomplete, and the central bank gives less weight to the output gap objective, compared to the constant return to scale ($\alpha = 0$) case. Then monetary policy should be more aggressive in bringing down inflation. This intuition will be clear from the robustness check section B when comparing the general case to the constant return to scale ($\alpha = 0$) calibration.

Our microfounded Phillips curve (Eq. 15) reflects the importance of both general myopia (\bar{m}) and inflation myopia (m_π^f) in the weight of inflation expectations in the current inflation determination, which is also the case in Gabaix (2019). Moreover, our Phillips curve gives a role to inflation myopia (m_π^f) in the weight of the output gap in the determination of current inflation, which is not the case in Gabaix (2019).

2.3 Welfare-relevant model

In the presence of nominal rigidities alongside real imperfections, the flexible price equilibrium is inefficient (Galí, 2015). Consequently, it is not optimal for the central bank to target this allocation, but it is optimal to target efficient allocation. Our model has to be expressed in terms of deviations with respect to the efficient aggregates so that the resulting variables become *welfare-relevant* ones.

Let us define the welfare-relevant output gap such that $x_t = y_t - y_t^e$, where y_t is the (log) output, y_t^e is the efficient output and y_t^n is the natural output (flexible-price output). Since $\tilde{y}_t = y_t - y_t^n$, linking the output gap and the welfare-relevant output gap gives $\tilde{y}_t = x_t + (y_t^e - y_t^n)$.

By exploiting this relationship, the behavioral IS curve in welfare-relevant output gap terms is

$$x_t = M\mathbb{E}_t x_{t+1} - \sigma (i_t - \mathbb{E}_t [\pi_{t+1}] - r_t^e) \quad (19)$$

where $r_t^e = r_t^n + (1/\sigma) (M\mathbb{E}_t [y_{t+1}^e - y_{t+1}^n] - (y_t^e - y_t^n))$ is the efficient interest rate

perceived by households.¹⁸

The behavioral Phillips curve in welfare-relevant output gap terms is

$$\pi_t = M^f \mathbb{E}_t [\pi_{t+1}] + \kappa x_t + u_t \quad (20)$$

where $M^f = \frac{\beta \theta \bar{m}}{1 - (1 - \theta) m_\pi^f}$ and $\kappa = \frac{(1 - \theta)(1 - \beta \theta) \Theta m_x^f}{1 - (1 - \theta) m_\pi^f} \left(\gamma + \frac{\phi + \alpha}{1 - \alpha} \right)$, and $u_t = \kappa (y_t^e - y_t^n)$ is a cost-push shock evolving according to an $AR(1)$ process such that $u_t = \rho_u u_{t-1} + \varepsilon_t^u$ and $\varepsilon_t^u \sim N(0; \sigma_u)$, *i.i.d.* over time.

The expectations in Eq. 19 and Eq. 20 are augmented by M and M^f , respectively, thus reducing the exaggerated weight given to expectations in the rational New Keynesian model (Blanchard, 2009).

3 Methodology

3.1 Myopia parameters

As optimal monetary policy is fully microfounded, our research question is independent of the determination of the myopia parameters. They are thereby considered exogenous but in the interval $[0, 1]$ as in Gabaix (2019). The endogenous case may be obtained by specifying cost functions for the agents, but we leave the myopia endogenization specification for further research.

Gabaix (2014) argues that inattention is derived from information's cost minimization, which yields to myopia parameters in the interval $[0, 1]$. By construction, New Keynesian models have to obey some heuristics, like convergence and stability, implying that the framework may not support all irrationality forms, such as over-attention, which is behaviorally plausible. Knowing these limitations, this type of model is preferred because of its tractability.

Although our model only focuses on under-reaction, it is also able to generate over-reaction (indirectly). As raised in Gabaix (2014), neglecting mitigating factors (i.e., negatively correlated additional effects) leads to overreaction. In other words, a consumer overreacts to an income shock if he pays too little attention to the fact that this shock is very transitory.

An essential feature of our theoretical framework allows for differentiated myopia—the fact that agents can be myopic about some economic variables. Wagner (1976) and Oates (1991) documented the revenue myopia as a consequence of several factors such as the complexity of the tax structure, the renter illusion with respect to property taxation, the income elasticity of the tax structure, the debt illusion, and the flypaper effect. Modigliani and Cohn (1979) have shown that because agents

¹⁸See Appendix A.4 for technical details.

do not understand the real effect of raising prices on interest rates, the market’s response to inflation is not rational. Bachmann et al. (2015) have found that spending attitudes are influenced by their nominal interest rate myopia. Other biases justify the adoption of differentiated myopia for our theoretical framework.

3.2 Calibration

Our main experiment uses calibrated values at 15% of myopia, corresponding to a calibration of the myopia parameters at 0.85. The detailed calibration for each model is described in Table 1. The robustness analysis using higher and extreme values for myopia parameters to demonstrate that our conclusions hold is available in Appendix B.

	Models						
	No myopia	Myopia					
	Rational	Interest rate	Output gap	Inflation	Revenue	General	Full
m_r	1	0.85	1	1	1	1	0.85
m_x^f	1	1	0.85	1	1	1	0.85
m_π^f	1	1	1	0.85	1	1	0.85
m_y	1	1	1	1	0.85	1	0.85
\bar{m}	1	1	1	1	1	0.85	0.85

Table 1: Calibration of the myopia parameters used for the simulation of each model.

Table 2 summarizes the values used to simulate our regimes. The standard parameters of our model are calibrated as in Galí (2015). Several robustness checks using various calibrations from the New Keynesian literature are presented in Appendix B.

Parameter	Calibration	Description
β	0.996	Static discount factor
γ	2	Household’s relative risk aversion
ε	9	Elasticity of substitution between goods
α	1/3	Return to scale
ϕ	5	Frisch elasticity of labor supply
θ	0.75	Probability of firms not adjusting prices
ρ_a	0.75	Technology shock persistence
ρ_u	0.75	Cost-push shock persistence

Table 2: Calibration of the other parameters used for the simulation of all the models. Source: Galí (2015).

3.3 Optimal policy

The optimal monetary policy question discussed in this paper requires an evaluation of the household's utility as the criterion that the central bank maximizes subject to the economy's constraints. As a cornerstone of our analysis, the microfounded welfare loss measure

$$\mathbb{W} = \frac{1}{2} \mathbb{E}_0 \sum_{t=0}^{\infty} \beta^t \left(\pi_t^2 + \frac{w_x}{w_\pi} x_t^2 \right) \quad (21)$$

where $w_\pi = \frac{\epsilon}{\Theta(1-\beta\theta)(1-\theta)}$ and $w_x = \gamma + \frac{\phi+\alpha}{1-\alpha}$ is derived from the second order approximation of the behavioral household's utility, as demonstrated in Appendix A.5.

4 Commitment

The central bank is assumed to be credible and able to commit to a policy plan that stabilizes the economy. It chooses a path for the output gap and inflation over the infinitely lived horizon to minimize a policy objective function, the welfare loss (Eq. 21).

4.1 Analytical solution

Solution 1 *The central bank problem solution under commitment yields to the following FOCs*

$$\pi_t + \varphi_t - \frac{M^f}{\beta} \varphi_{t-1} = 0 \quad (22)$$

$$\frac{w_x}{w_\pi} x_t - \kappa \varphi_t = 0 \quad (23)$$

where φ_t is the Lagrange multiplier associated with the policy problem.

Proposition 1 *A form of PLT is optimal when $\bar{m} = 1$ and $m_\pi^f = 1$, and a form of IT is optimal when this condition is not satisfied.*

Proof. The Lagrangian of the central bank's problem is

$$L_t = \mathbb{E}_t \sum_{t=0}^{\infty} \beta^t \left[\frac{1}{2} \left(\pi_t^2 + \frac{w_x}{w_\pi} x_t^2 \right) + \varphi_t (\pi_t - \kappa x_t - M^f \pi_{t+1}) \right] \quad (24)$$

Deriving the Lagrangian with respect to π_t yields the first FOC (Eq. 22). Deriving the latter with respect to x_t yields the second FOC (Eq. 23). Consequently,

we can write Eq. 22 in terms of the price level

$$p_t + \varphi_t = p_{t-1} + \frac{M^f}{\beta} \varphi_{t-1} \quad (25)$$

Two cases can be distinguished: (i) The case where the price level is stationary, i.e., $\frac{M^f}{\beta} = 1$. Such a case prevails when $\bar{m} = 1$ and $m_\pi^f = 1$, and a form of PLT is optimal. (ii) Otherwise, a form of IT is optimal. ■

Note that by combining Eq. 22 and Eq. 23 we obtain the following central bank targeting rule

$$\pi_t = -\frac{w_x}{\kappa w_\pi} \left(x_t - \frac{M^f}{\beta} x_{t-1} \right) \quad (26)$$

which has to be satisfied at every period to obtain optimal outcomes. Isolating the expression of the price level from Eq. 26 leads to

$$p_t = -\frac{w_x}{\kappa w_\pi} \left(x_t + \left(1 - \frac{M^f}{\beta} \right) \sum_{j=0}^{t-1} x_j \right) \quad (27)$$

Applying the Proposition 1 to Eq. 27, and considering the case of optimal PLT where $\bar{m} = 1$ and $m_\pi^f = 1$, we end up with the following targeting rule

$$p_t = -\frac{w_x}{\kappa w_\pi} x_t$$

which satisfies the fact that the price level is stationary, as the output gap tends to be null in the long term. The PLT is an optimal outcome for monetary policymaking even in the presence of other forms of myopia such as interest rate, revenue, or output gap. The only requirement for this form of targeting to be optimal is the full attentiveness to inflation developments. Indeed, a central bank under this regime sets a target for the price level and adjusts its decisions accordingly. In case of a positive cost-push shock, for instance, price level jumps to a new level while the output gap opens up. To achieve its target, the central bank has to engineer a deflation. Consider the case where economic agents are myopic to inflation ($m_\pi^f \neq 1$), the recessionary effect of monetary policy on output does not transmit completely to the price level (through Eq. 27). Consequently, monetary policy has to engineer a second deflationary round to stabilize the price level, and so on until the target is achieved at the expense of depressing economic activity. Thus, for PLT to be socially optimal, a minimal condition of full attentiveness to inflation has to be satisfied even with the presence of the remaining forms of myopia.

In contrast, Gabaix (2019) concluded that PLT is not optimal with behavioral agents, but our result points that this conclusion is incomplete. The proposition

derived in this section indicates the optimality of PLT in many behavioral cases. Referring to the cases described in 1, the cases of interest rate, output gap, and revenue myopia satisfy the proposition (Section 4.1), all exhibiting a form of PLT.

Under interest rate, output gap, and revenue myopia, people perfectly foresee inflation as there is no inflation myopia. Consequently, as the central bank (also) monitors *perfect* inflation expectations, it can implement PLT appropriately, which delivers the first best solution.

In response to a cost-push shock, the central bank's commitment to engineering a deflation in the future has implications for the current inflation to the extent that behavioral agents—households and firms—are forward-looking in terms of this specific variable while myopic to other macroeconomic variables. The conclusion that bounded rationality implies suboptimality of PLT is shortsighted. Digging into different forms of bounded rationality shows that this targeting might be optimal in the cases highlighted earlier and that IT is optimal in the remaining cases.

The takeaway from this analysis is that, contrary to the existing monetary economics literature, there is no definitive answer in term of the optimal conduct of monetary policy. Depending on which myopia characterizing households and firms prevails, a central bank must choose the corresponding targeting.

4.2 Simulation and welfare

Fig. 1 presents the responses of the economy to a 1 percent cost-push shock. The cost-push shock implies a trade-off between the output gap and inflation. The intensity of such a trade-off differs slightly depending on the form of myopia.

For instance, full myopia entails a substantial increase in inflation with a significant drop in output. Such deviations require a strong reaction from the central bank. Furthermore, in this (full) myopia case, we notice that the price level never returns to its steady state after a cost-push shock, which corroborates the analytical result about the suboptimality of PLT in this particular case.

Whenever people are myopic to inflation, PLT is suboptimal while IT is optimal due to the welfare cost induced by the central bank's decisions to stabilize the price level in a behavioral world (where people are boundedly rational regarding inflation).

Concerning the output gap myopia, revenue myopia, and interest rate myopia, we notice that, following a cost-push shock, inflation rises on impact but decreases to deflation after some periods. In both cases, the price level reaches its steady-state value, which makes these types of myopia entail a form of PLT as an optimal monetary policy.

Regarding the central bank's reactions, it is worth noting that the impulse re-




Figure 1: Impulse response functions of inflation, price level, output and interest rate following a 1% cost-push shock under commitment for each model.

sponse function amplitudes in the cases of the output gap, inflation, and revenue myopia are very close to the rational case. The only cases where a strong central bank reaction is required are the interest rate myopia, general myopia and full myopia. In these cases, the optimal policy is set in a way to sharply offset the shock, and then it does not allow the price level to recover its steady-state value. Instead, it finds a new steady-state value. However, in the remaining cases, the optimal required action is more smooth, and the central bank improves the policy trade-off in a way that allows a deflation to operate and then the price level to be stationary.

To sum up, the impulse response results confirm the analytical result derived earlier (Section 4.1) in addition to emphasizing that the optimal responses of the central bank, in the presence of behavioral agents, are not always strong compared to the rational benchmark. These results are robust to different model and myopia calibrations that we use and report in Appendix B.

Table 3 presents the welfare losses for each bounded rationality case.

No myopia	Myopia					
Rational	Interest rate	Output gap	Inflation	Revenue	General	Full
0.174	0.174	0.227	0.190	0.174	0.176	0.248

Table 3: Welfare losses under commitment.

Although the rational case generates the lowest welfare loss, which is intuitive given the perfect foresight assumption, in this case, interest rate and revenue my-

opia provide both the same welfare losses as the rational benchmark. The reason is simple. The central bank loss does not penalize deviations of interest rate or revenue, while in these two myopia cases, agents are well-informed about output and inflation. Moreover, the general myopia is very close to these cases. As a result, bounded rationality is not necessarily welfare decreasing.

5 Discretion

According to Plosser (2007), when the central bank is “not bound by previous actions or plans and thus is free to make an independent decision every period”, monetary policy is called *discretionary*. In such a case, the central bank makes whatever decision is optimal in each period without committing itself to any future actions.

In this section, we characterize the second-best solutions of the central bank’s optimization problem following a cost-push shock.

5.1 Analytical solution

In this regime, the central bank minimizes the welfare loss related to the decision period, taking into account that expectations are given, which yields to the following proposition.

Proposition 2 *Discretionary central bank has to obey to the following targeting criterion when setting its optimal policy:*

$$\pi_t = -\frac{w_x}{\kappa w_\pi} x_t \quad (28)$$

Proof. It is sufficient to write the Lagrangian and derive with respect to both endogenous variables to obtain FOCs. Once combined, we end up with the targeting rule for the central bank in this case. ■

After a cost-push shock, a discretionary central bank has to keep this proposition satisfied to minimize the welfare loss. When inflationary pressures arise, the policymaker has an incentive to drive output below its efficient level to accommodate the cost-push shock. While this proposition is silent about the influence of bounded rationality on a discretionary policy, the size of both output and inflation deviations due to the cost-push shock depends on myopia. To make this clear, we replace the Eq. 28 in the Phillips curve and solve forward, which yields the following expression for inflation

$$\pi_t = \frac{\frac{w_x}{w_\pi}}{\frac{w_x}{w_\pi} + \kappa^2 - \frac{w_x}{w_\pi} M^f \rho_u} u_t \quad (29)$$

and by using the targeting rule Eq. 28, we obtain an expression for the output gap

$$x_t = \frac{-\kappa}{\frac{w_x}{w_\pi} + \kappa^2 - \frac{w_x}{w_\pi} M^f \rho_u} u_t \quad (30)$$

These expressions state that the central bank has to let the output gap and inflation deviate proportionally to the cost-push shock (u_t). Bounded rationality influences the magnitudes of these deviations through κ , which depends on output gap and inflation myopias, m_x^f and m_π^f respectively, and through M^f , which depends on the general and inflation myopia, \bar{m} and m_π^f respectively.

The optimal policy response entails an indeterminate price level but determinate inflation, which suggests a form of IT as the preferred regime for a central bank under discretion.

Although the type of myopia considered could impact the magnitudes of the reactions to a particular shock, bounded rationality under discretion does not impact the choice of the policy regime. The rationale under such a proposition is that, in this case, monetary policy takes expectations as exogenous and seek to only accommodate the shock in the current period. However, bounded rationality influences the expected reaction of macro variables to this shock, as highlighted in Eq. 29 and Eq. 30 and shown by the impulse response functions presented in the following section.

5.2 Simulation and welfare

A cost-push shock is assumed to understand the obtained optimal equilibrium (Eq. 29 and Eq. 30) by examining inflation and output gap reactions under different myopia scenarii. Fig. 2 presents the impulse response functions to a 1 percent cost-push shock under an optimal discretionary monetary policy.

As discussed in Section 5.1, we can assess the deviation of both the output gap and inflation reacting to a cost-push shock. Differences arising in each type of myopia reflect the way myopia interacts with the proposed solution for inflation and the output gap (Eq. 29 and Eq. 30).

Two remarks are worth noting here. First, the optimal monetary policy reaction seeks to increase the policy rate to accommodate the inflation increase but aggressively compared to the rational benchmark—except for the case of revenue myopia. Second, as mentioned previously, the price level is not stationary in any case, which suggests an IT regime as the desirable monetary policy.

As reported in Table 4, the evaluation of welfare losses reveals that the optimal policy is better under general myopia than under the rational benchmark.

Although this result could seem counterintuitive, one should remember that this




Figure 2: Impulse response functions of inflation, price level, output and interest rate following a 1% cost push shock under discretion for each model.

No myopia	Myopia					
Rational	Interest rate	Output gap	Inflation	Revenue	General	Full
0.270	0.270	0.386	0.287	0.270	0.236	0.341

Table 4: Welfare losses under discretion.

form of myopia (general myopia) impacts the level of expectations of all macroeconomic variables or the model. In this case, people's expectations are distorted, which is consistent with a discretionary policymaker.

6 Simple rules

In this section, we determine the optimal coefficient values that minimize the central bank loss function of the various simple rules described in Table 5.

The instrument rules described in Table 5 reproduce the central bank's instrument rules when reacting only to the targeted variable, in a strict targeting sense (rules S1 to S4), and when reacting to real fluctuations in addition to its primary target, in a flexible sense (rules F1 to F4). Note that, in some cases, the central bank does not restrict its attention only to endogenous variables, which is why the monetary policy shock (ε_t^{mp}) is added to reflect the deviations of the central bank from its rule.

Hereafter, we provide the optimal coefficient values (Section 6.1) and welfare losses (Section 6.2).

Name	Targeting regime	Instrument-rule
F1	Flexible inflation	$i_t = \phi_\pi \pi_t + \phi_y \tilde{y}_t + \varepsilon_t^{mp}$
F2	Flexible price level	$i_t = \phi_p p_t + \phi_y \tilde{y}_t + \varepsilon_t^{mp}$
F3	Flexible NGDP growth	$i_t = \phi_g (\pi_t + \Delta \tilde{y}_t) + \phi_y \tilde{y}_t + \varepsilon_t^{mp}$
F4	Flexible NGDP level	$i_t = \phi_n (p_t + \tilde{y}_t) + \phi_y \tilde{y}_t + \varepsilon_t^{mp}$
S1	Strict inflation	$i_t = \phi_\pi \pi_t + \varepsilon_t^{mp}$
S2	Strict price level	$i_t = \phi_p p_t + \varepsilon_t^{mp}$
S3	Strict NGDP growth	$i_t = \phi_g (\pi_t + \Delta \tilde{y}_t) + \varepsilon_t^{mp}$
S4	Strict NGDP level	$i_t = \phi_n (p_t + \tilde{y}_t) + \varepsilon_t^{mp}$

Table 5: Regime names, descriptions and simple rules

6.1 Optimal coefficient values

Table 6 reports the optimal values¹⁹ of ϕ_π , the weight on inflation; ϕ_y , the weight on the output gap; ϕ_p , the weight on the price level; ϕ_g the weight on NGDP growth; and ϕ_n the weight on the NGDP level for different monetary policy rules.

	F1		F2		F3		F4		S1	S2	S3	S4
	ϕ_π	ϕ_y	ϕ_p	ϕ_y	ϕ_g	ϕ_y	ϕ_n	ϕ_y	ϕ_π	ϕ_p	ϕ_g	ϕ_n
No (rational)	1.96	0.25	0.33	0.0	2.62	0.5	0.17	0.0	2.37	0.34	3.90	0.17
Interest rate	2.44	0.20	0.39	0.0	3.32	0.5	0.20	0.0	3.11	0.40	4.00	0.20
Output gap	1.39	0.32	0.26	0.0	1.81	0.5	0.13	0.0	2.02	0.27	3.43	0.13
Inflation	1.43	0.27	0.30	0.0	1.55	0.5	0.15	0.0	1.99	0.31	3.26	0.15
Revenue	2.03	0.21	0.33	0.0	2.63	0.5	0.17	0.0	2.37	0.34	3.91	0.17
General	2.05	0.14	0.56	0.0	1.61	0.5	0.25	0.0	2.38	0.58	3.34	0.25
Full	1.54	0.18	0.49	0.0	1.10	0.5	0.21	0.0	2.10	0.50	2.82	0.21

Table 6: Coefficients of the optimal simple rules (F1 to S4) under different myopia.

As shown in Table 6, the inflation coefficients under the flexible and strict IT regimes (F1 and S1) are strictly greater than one in all myopia cases, which is in line with the stability condition (Galí, 2008, 2015). As the results show, myopia does impact the coefficients of the optimal simple rules. Consequently, people's perceptions of future macroeconomic dynamics lead the central bank to react differently under each regime for each myopia.

Compared to the rational case, interest rate myopia appears to increase the sensitivity of the policy instrument to the central bank target. Monetary policy is transmitted to the output gap and inflation through the IS and Phillips Curve equations, conditional on the model coefficients influenced by behavioral myopia parameters. Agents' myopia to the future interest rate weakens the transmission of monetary policy to the output gap. To control its target, the central bank has to react aggressively in order to send the appropriate signal. Intuitively, the policy-

¹⁹Optimizations are based on the calibration presented in Section 3.2.

maker needs to strongly signal its control over its target when people misperceive the interest rate for each targeting case.

For all considered rules, the output gap myopia decreases the sensitivity of the interest rate to the central bank's target compared to the rational case. However, the reaction to the output gap becomes stronger compared to the rational case in the flexible IT rule. The reason for this shift is related to the fact the output gap myopia implies that the transmission from the output gap to inflation becomes weak, while the other channel from the interest rate to output gap remains unaffected by this myopia. For instance, to have the desired impact on inflation, the central bank reacts strongly to the output gap but softly to inflation in F1. By misperceiving the output gap dynamics, this economy lacks the pass-through from the output gap to the nominal variables, which are the targeted variables for the central bank. Then, the central bank reaction function is less sensitive to its nominal target compared to the rational case.

Regarding inflation myopia, the sensitivity to targeted variables is smaller than the rational case due to the higher transmission from inflation expectations and the output gap to inflation. The case for revenue myopia is quite similar, given that this myopia increases the feedback from output gap expectations and the interest rate to the output gap, which feeds to inflation, while the transmission from the output gap to inflation remains constant. That is why we see such similar coefficients in reaction to the targeted variable compared to the rational case.

The central bank should react aggressively to curb expectations and impact the desired variables under general and full myopia.

Another set of results is derived when comparing the considered targeting regimes. The characteristics of the optimal rules differ in their sensitivity to different myopia cases. The central bank appears to be more sensitive to its target when operating under strict targeting compared to flexible targeting.

The nominal income coefficients associated with strict NGDP growth targeting (S3) are higher than the flexible NGDP growth targeting coefficients (F3) across all types of myopia, a result in line with the literature (Rudebusch, 2002; Benchimol and Fourçans, 2019). As these coefficients are also larger than one, they respect the necessary stability conditions (Taylor principle). Table 6 reveals that when the central bank targets the NGDP level (F4 and S4) or the price level (F2 and S2), both in the strict and flexible senses, the coefficients are positive but lower than one, a result in line with Rudebusch (2002).

If we compare PLT in flexible and strict senses, we find similar results. The same result is found when comparing NGDP level targeting in flexible and strict forms. When the central bank targets a form of price level or NGDP objective, the output

gap objective becomes not desirable. This result consists of a *divine coincidence* between stabilizing the price level and the output gap. Indeed, a form of PLT leads to self-stabilizing dynamics for the output gap. If the price level deviation from its target increases, say a decrease (increase) from its target, the central bank takes correcting measures to increase (decrease) inflation in the future to restore the targeted price level, inducing a lower real interest rate that contributes to boosting the output gap.

All the optimal coefficients depend more or less on agent myopia, and it is clear that interest rate myopia delivers the most substantial amplitude compared to other types of myopia under IT and NGDP growth targeting. Under price level and NGDP level targeting regimes, it is general myopia that delivers the highest coefficients.

For the optimal values of ϕ_p in rules F2 and S2, regardless of whether the central bank targets the price level flexibly or strictly, the sensitivity of the policymaker's instrument to the price level does not vary significantly between the flexible and strict regimes. This is also the case between rules F4 and S4.

The coefficient of the output gap varies across the different types of myopia and rules considered. First, the rules reflecting flexible PLT (F2) and NGDP level targeting (F4) show null optimal values for the output gap, which suggests that the central bank does not have to care about real fluctuations under these regimes. Second, the coefficient on the output gap in the flexible IT rule (F1) displays a slight sensitivity to myopia.

6.2 Which rule best describes the first best solution?

The performance of policy rules is compared using the same microfounded welfare criterion as in Section 5 and Section 4. The welfare losses for each rule are reported in Table 3.

Flexible targeting rules do not necessarily induce welfare losses compared to strict rules. Most flexible targeting rules generate similar welfare losses compared to their corresponding strict targeting rules. For instance, welfare losses are identical between F1 and S1.

Strict PLT delivers the lowest welfare among the considered rules. Note that the welfare losses associated with this rule are similar to the flexible PLT rule through different myopia cases. The reason behind this equivalence lies in the optimal value of the output gap feedback to the interest rate in rule F2, which is null, a case for a divine coincidence when the central bank is pursuing a price level objective.

Moreover, the rational case delivers similar welfare losses to interest rate and revenue myopia cases as in the previous results (Tables 3 and 4).

Myopia	Rational	0.2093	0.1766	0.2161	0.1855	0.2093	0.1762	0.2167	0.1852
	Interest rate	0.2093	0.1766	0.2162	0.1857	0.2094	0.1763	0.2168	0.1854
	Output gap	0.2848	0.2317	0.2976	0.2456	0.2848	0.2310	0.2993	0.2450
	Inflation	0.2264	0.1923	0.2361	0.2016	0.2264	0.1919	0.2378	0.2013
	Revenue	0.2093	0.1766	0.2161	0.1855	0.2093	0.1762	0.2167	0.1853
	General	0.1997	0.1773	0.2110	0.1840	0.1997	0.1772	0.2134	0.1838
	Full	0.2849	0.2518	0.3091	0.2612	0.2849	0.2517	0.3205	0.2609
			F1	F2	F3	F4	S1	S2	S3
		Regimes							

Figure 3: Welfare losses under optimal simple rules. Note: the shading scheme is defined separately in relation to each column. The lighter the shading is, the smaller the welfare loss.

Regarding other bounded rationality cases, it is clear that across those targeting rules, output gap and full myopia imply the most important welfare losses compared to the other cases. However, general myopia, combined with appropriate central bank action, sometimes yields to smaller welfare losses compared to the rational case as in the discretion case (Table 4).

As the welfare analysis shows (Table 3), the best monetary policy rule (that delivers the lowest welfare loss) is the strict PLT rule, whatever type of myopia considered. While this result is interesting, it demonstrates the inability of these simple rules to replicate the first best solution under commitment, which emphasizes that the optimal policy depends on the type of myopia characterizing agents.

7 Discussion

Analyzing optimal monetary policy through the lens of a behavioral perspective leads to a richer set of results. Some results corroborate the findings in the rational expectations literature about optimal monetary policy—as in section 4 when setting myopia parameters to 1. Other results contrast with the views of the behavioral macroeconomic literature—when myopia parameters are different from 1. Our results

shed light on an old debate about the inability of simple rules to constitute a guideline for monetary policy.

Relaxing the rational agent hypothesis contributes, in the case of commitment, to addressing one of the critiques of the New Keynesian model, namely, the persistence of macroeconomic variables with respect to monetary policy shocks (Walsh, 2017; Fuhrer and Moore, 1995). We come to the same conclusion as Woodford (2010), in which near-rational expectations are used, about the history dependence of the targeting rule under commitment. One can infer that assuming more *realistic* agents in the New Keynesian model would provide a more accurate replication of the impact of monetary policy.

Our result on the optimality of a form of PLT in the cases of interest rate, output gap or revenue myopia and the optimality of a form of IT in the remaining cases departs from the existing monetary economics literature but also from Gabaix (2019). Bounded rationality gives reason to both sides, the proponent of PLT and those in favor of IT, by setting the borders between the appropriate use of each targeting regime depending on the agents' myopia. While this departure from rationality complicates expectation management, it offers a rich set of policy regimes—IT and PLT—for the policymaker to choose given the state of the world—myopia.

The baseline rational New Keynesian framework recommends a form of PLT as the optimal policy (Galí and Gertler, 1999; Woodford, 2003). This recommendation is nested in our results by shutting down myopia parameters (in section 4). Deviations from this benchmark like in the rational inattention framework (Maćkowiak and Wiederholt, 2009, 2015) find small differences in terms of welfare compared to the rational case, which does not alter the policy conclusions of the rational expectations model.

Learning models, as surveyed in Eusepi and Preston (2018), conclude that a form of PLT could be a proxy for the optimal policy.

By deviating from the rational agent hypothesis and using price setters' information stickiness, Ball et al. (2005) find that flexible PLT is optimal. Honkapohja and Mitra (2018) employs a nonlinear New Keynesian model under learning to show that PLT performs well depending on the credibility of the central bank. Using different deviations from rationality, namely bounded rationality, supports the finding of PLT optimality. Gabaix (2019) completely dismisses the latter result and concludes that PLT is suboptimal.

By exploring all possible forms of bounded rationality, we emphasize the optimality of PLT in some cases, as the existing literature does, while validating the results of Gabaix (2019) only under some specific bounded rationality configurations. In light of the real experiment led by Amano et al. (2011), who finds that

PLT is better suited to *real* agents' beliefs, which are presumably boundedly rational, we cannot ignore that PLT is the prescribed monetary policy.

Our robustness analysis (Appendix B) shows that our results are robust to the model's calibration of the structural parameters. It also shows that high general myopia always improves welfare losses under commitment, discretion, and optimal simple rule regimes. Indeed, bounded rationality is not necessarily associated with decreased welfare. Extreme general myopia can increase welfare whatever the monetary policy regime.

Regarding our result under commitment, one could expect that optimal simple rules would allow us to replicate the first best solution emphasizing IT in some cases (small welfare losses) and PLT in the remaining cases. However, under these instrument rules, the welfare loss evaluation points to the desirability of strict PLT as a proxy for the optimal monetary policy, regardless of the bounded rationality type. Such a result is in sharp contrast with the policy prescription under commitment.

This result recalls the old debate regarding the instrument rules versus targeting rules, as emphasized in Svensson (2003). Mechanical instrument rules, as a guideline for monetary policy, are likely to be inadequate for optimizing and forward-looking central banks. Svensson (2003) argues that the concept of targeting rules is more appropriate to the forward-looking nature of monetary policy. In the same vein, the inability of simple rules to replicate the commitment solution is a clear case of the shortcomings related to this kind of monetary policy conception. Managing expectations in a behavioral world needs to deviate from a mechanical rule and enlarge the scope to a targeting rule that provides more room for switching policies as people's perceptions change.

8 Policy implications

Following the Global Financial Crisis, central bank and policy institution members called for an in-depth revision of the IT framework, which shaped the policy decisions of major central banks over several decades (Bernanke, 2017; Blanchard and Summers, 2019; Evans, 2018). Some policymakers advocate the appropriateness of PLT as a measure to overcome the challenges brought by the Zero Lower Bound (Bernanke, 2017). Others want to retain the current IT framework and make some adjustment to its parameters, such as raising the inflation target (Blanchard and Summers, 2019) or allowing interest rates to be negative. Even before the crisis, the debate between IT and PLT was an old debate of the modern monetary policy era (Svensson, 1999).

Our result bridges the gap between these two competing views about which

kind of monetary policy targeting is optimal. Both forms of targeting, namely PLT and IT, could be optimal but in different circumstances. Our findings show that assessing bounded rationality is a crucial indicator for the central bank to decide whether it has to pursue an IT or PLT.

The evaluation of the instrument rules indicates the desirability of strict PLT over the other monetary policy targeting regimes, which is in line with the literature surveyed by Hatcher and Minford (2016) in the rational case. However, regarding the bounded rationality cases, this homogeneity of the choice of the targeting rule leaves us with much concern about the inability of these simple instrument rules to replicate the optimal policy as a first best. This result questions the usefulness of these rules for stabilizing the economy while taking into account bounded rationality as an essential policymaking ingredient.

The inability of simple rules to replicate the first best solution calls for a re-consideration of their roles in the conduct of monetary policy. Furthermore, their mechanical nature is not adapted to the changing nature of inattention that agents experience in different circumstances. We join Svensson (2003) in calling for including *targeting rules* (as derived in Proposition 1) to the central banking apparatus in setting monetary policy decisions.

Overall, agents' expectations matter for monetary policy conduct. A concrete illustration is policymakers' desire to *educate* the public through intensive communication. Central banks have, for several decades, educated agents in economics to increase public understanding and trust of their monetary policies, among other objectives. Such a program may be perceived as an effort to attenuate myopia, thus guiding agents to rationality. Even if bounded rationality is not a curable disease—although not always a disease, as myopia sometimes improves welfare—and is inherent to human functioning, it should motivate central banks to act using the correct tools by taking into account agents' myopia to improve welfare. Convincing central bank staffs to explore, monitor and analyze agents' myopia constitutes a relevant policy recommendation of this paper. Assessing the degree to which economic agents are myopic is one of the areas that central banks should invest in more. Borrowing an analogy from Thaler (2016), the central bank should invest in studying the degree to which *Homo sapiens* are myopic and act consistently rather than educate people and attempt to transform humans into *Homo economicus*.

9 Conclusion

Optimal monetary policy is assessed in a behavioral New Keynesian framework to show that the first best solution depends on the type of myopia characterizing

agents. While a form of PLT is optimal in some myopia cases, IT is more appropriate in the remaining cases.

No definitive answer about the targeting policy to adopt in a behavioral setting can be drawn. Neither IT nor PLT is consistently optimal under all states of the world.

Bounded rationality matters for the conduct of monetary policy. In an attempt to implement the commitment result through an instrument rule, we find that optimal simple rules favor strict PLT in all bounded rationality cases we consider. Such a result leaves us with a puzzling observation about the replication of the first best solution.

The inability of simple rules to replicate the first best solution calls for a reconsideration of their roles in the conduct of monetary policy. This finding opens a new reflection about the instrument rules in an economy with behavioral agents. While these types of rules provide policymakers with a simple monetary policy tool, it is not clear what role these rules could play in a behavioral world. Bounded rationality is not necessarily associated with decreased welfare. Several forms of economic inattention, especially extreme ones, can increase welfare. By contrast, output gap myopia implies significant welfare losses compared to the rational case. The central bank has to assess and monitor different types of myopia to optimally conduct monetary policy.

References

- Akerlof, G. A., Yellen, J. L., 1987. Rational models of irrational behavior. *American Economic Review* 77 (2), 137–142.
- Amano, R., Engle-Warnick, J., Shukayev, M., 2011. Price-level targeting and inflation expectations: experimental evidence. Staff working papers, Bank of Canada.
- Andrade, P., Le Bihan, H., 2013. Inattentive professional forecasters. *Journal of Monetary Economics* 60 (8), 967–982.
- Bachmann, R., Berg, T. O., Sims, E. R., 2015. Inflation expectations and readiness to spend: cross-sectional evidence. *American Economic Journal: Economic Policy* 7 (1), 1–35.
- Ball, L., Mankiw, N. G., Reis, R., 2005. Monetary policy for inattentive economies. *Journal of Monetary Economics* 52 (4), 703–725.
- Benchimol, J., Fourçans, A., 2019. Central bank losses and monetary policy rules:

- a DSGE investigation. *International Review of Economics and Finance* 61 (1), 289–303.
- Bernanke, B. S., 2017. Monetary policy in a new era. In: Prepared for conference titled "Rethinking Macroeconomic Policy", Peterson Institute for International Economics, Washington DC, October. pp. 1–49.
- Blanchard, O. J., 2009. The state of macro. *Annual Review of Economics* 1 (1), 209–228.
- Blanchard, O. J., 2018. On the future of macroeconomic models. *Oxford Review of Economic Policy* 34 (1-2), 43–54.
- Blanchard, O. J., Summers, L. H., 2019. *Evolution or Revolution? Rethinking Macroeconomic Policy after the Great Recession*. Cambridge, MA: MIT Press.
- Calvo, G., 1983. Staggered prices in a utility-maximizing framework. *Journal of Monetary Economics* 12 (3), 383–398.
- Clarida, R., Galí, J., Gertler, M., 1999. The science of monetary policy: a New Keynesian perspective. *Journal of Economic Literature* 37 (4), 1661–1707.
- Coibion, O., Gorodnichenko, Y., 2015. Information rigidity and the expectations formation process: a simple framework and new facts. *American Economic Review* 105 (8), 2644–2678.
- De Grauwe, P., 2012. *Lectures on behavioral macroeconomics*. No. 9891 in *Economics Books*. Princeton, NJ: Princeton University Press.
- Eusepi, S., Preston, B., 2018. The science of monetary policy: an imperfect knowledge perspective. *Journal of Economic Literature* 56 (1), 3–59.
- Evans, C. L., 2018. Some practical considerations for monetary policy frameworks. Speech at the Shadow Open Market Committee meeting, Manhattan Institute, New York City.
- Evans, G. W., Honkapohja, S., 2012. *Learning and expectations in macroeconomics*. Princeton, NJ: Princeton University Press.
- Evans, G. W., Honkapohja, S., 2013. Learning as a rational foundation for macroeconomics and finance. In: Frydman, R., Phelps, E. S. (Eds.), *Rethinking Expectations: The Way Forward for Macroeconomics*. Princeton University Press, Ch. 2, pp. 68–111.

- Fuhrer, J. C., Moore, G., 1995. Inflation persistence. *Quarterly Journal of Economics* 110 (1), 127–159.
- Gabaix, X., 2014. A sparsity-based model of bounded rationality. *Quarterly Journal of Economics* 129 (4), 1661–1710.
- Gabaix, X., 2019. A behavioral New Keynesian model. Mimeo, Harvard University.
- Galí, J., 2008. *Monetary policy, inflation and the business cycle: an introduction to the New Keynesian framework*, 1st Edition. Princeton, NJ: Princeton University Press.
- Galí, J., 2015. *Monetary policy, inflation and the business cycle: an introduction to the New Keynesian framework*, 2nd Edition. Princeton, NJ: Princeton University Press.
- Galí, J., Gertler, M., 1999. Inflation dynamics: a structural econometric analysis. *Journal of Monetary Economics* 44 (2), 195–222.
- Gennaioli, N., Ma, Y., Shleifer, A., 2016. Expectations and investment. *NBER Macroeconomics Annual* 30 (1), 379–431.
- Hatcher, M., Minford, P., 2016. Stabilisation policy, rational expectations and price-level versus inflation targeting: a survey. *Journal of Economic Surveys* 30 (2), 327–355.
- Honkapohja, S., Mitra, K., 2018. Price level targeting with evolving credibility. *Research Discussion Papers 5/2018*, Bank of Finland.
- Kahneman, D., 1973. *Attention and effort*. Vol. 1063. Englewood Cliffs, NJ: Prentice-Hall.
- Maćkowiak, B., Wiederholt, M., 2009. Optimal sticky prices under rational inattention. *American Economic Review* 99 (3), 769–803.
- Maćkowiak, B., Wiederholt, M., 2015. Business cycle dynamics under rational inattention. *Review of Economic Studies* 82 (4), 1502–1532.
- Modigliani, F., Cohn, R. A., 1979. Inflation, rational valuation and the market. *Financial Analysts Journal* 35 (2), 24–44.
- Oates, W., 1991. On the nature and measurement of fiscal illusion: a survey. In: Oates, W. (Ed.), *Studies in Fiscal Federalism*. Brookfield, VT: Edward Elgar, pp. 431–448.

- Plosser, C. I., 2007. Credibility and commitment: a speech presented to the New York Association for Business Economics, March 6, 2007, and as the Hutchinson Lecture, University of Delaware, April 10, 2007. Speech 4, Federal Reserve Bank of Philadelphia.
- Rudebusch, G., 2002. Assessing nominal income rules for monetary policy with model and data uncertainty. *Economic Journal* 112 (479), 402–432.
- Sims, C. A., 2003. Implications of rational inattention. *Journal of Monetary Economics* 50 (3), 665–690.
- Stiglitz, J. E., 2011. Rethinking macroeconomics: what failed, and how to repair it. *Journal of the European Economic Association* 9 (4), 591–645.
- Svensson, L. E. O., 1999. Price-level targeting versus inflation targeting: a free lunch? *Journal of Money, Credit and Banking* 31 (3), 277–295.
- Svensson, L. E. O., 2003. What is wrong with Taylor rules? Using judgment in monetary policy through targeting rules. *Journal of Economic Literature* 41 (2), 426–477.
- Taylor, J. B., 1993. Discretion versus policy rules in practice. *Carnegie-Rochester Conference Series on Public Policy* 39 (1), 195–214.
- Thaler, R. H., 2016. Behavioral economics: past, present, and future. *American Economic Review* 106 (7), 1577–1600.
- Wagner, R. E., 1976. Revenue structure, fiscal illusion, and budgetary choice. *Public Choice* 25 (1), 45–61.
- Walsh, C., 2017. *Monetary theory and policy*. Cambridge, MA: MIT Press.
- Woodford, M., 2003. *Interest and prices: foundations of a theory of monetary policy*. Princeton, NJ: Princeton University Press.
- Woodford, M., 2010. Robustly optimal monetary policy with near-rational expectations. *American Economic Review* 100 (1), 274–303.
- Woodford, M., 2013. Macroeconomic analysis without the rational expectations hypothesis. *Annual Review of Economics* 5 (1), 303–346.

10 Appendix

A Derivations

A.1 IS curve

In this section, we use the Feynman-Kac methodology to derive the Taylor expansion of the consumption deviations.

The Lagrangian of the optimization problem is

$$L = \sum_{t=0}^{\infty} \beta^t u(c_t, N_t) + \sum_{t=0}^{\infty} \beta^t \lambda_t^k (k_t - (1 + r_t)(k_{t-1} - c_{t-1} + y_{t-1})) \quad (31)$$

where $r_t = \bar{r} + m_r \hat{r}_t$, $y_t = \bar{y} + m_y \hat{y}_t$, and λ_t is the Lagrange multiplier, which is equal to $\partial V(k_t) / \partial k_t$, the derivative of the value function with respect to k .

The value function is defined as²⁰ $V(k_t) = \max_c \{u(c) + \beta V(k_{t+1})\}$

At the optimum, the agent solves the following problem: $V(k) = \max_{c,k} \{L\}$.

The envelope theorem implies that

$$\frac{\partial V}{\partial r_t} = \frac{\partial L}{\partial r_t} = \beta^t \left[\frac{\partial u(c_t)}{\partial r_t} + \beta \lambda_t^k (k_t - c_t + y_t) \right] \quad (32)$$

By deriving this expression with respect to k_0 , we find that

$$\frac{\partial}{\partial k_0} \left(\frac{\partial V}{\partial r_t} \right) = \beta^t \frac{\partial k_t}{\partial k_0} \frac{\partial}{\partial k_t} \left[\frac{\partial u(c_t)}{\partial r_t} + \beta \lambda_t^k (k_t - c_t + y_t) \right] \quad (33)$$

By applying this formula to the problem at hand and taking into account the derivative of the value function in the default case, $\lambda_t^k = \frac{\partial V}{\partial k_t} = \left(\bar{y} + \frac{\bar{r} \phi}{R \phi + \gamma} k \right)^{-\gamma}$, we obtain

$$V_{r,k} = \beta^t \frac{\partial}{\partial k_t} \left[\beta \left(\frac{\bar{r} \phi}{R \phi + \gamma} k_t + \bar{y} \right)^{-\gamma} \frac{k_t}{R} \right] \quad (34)$$

where $V_{r,k} = \frac{\partial}{\partial k_0} \left(\frac{\partial V}{\partial r_t} \right)$.

By deriving and simplifying the expression above, we obtain

$$V_{r,k} = \frac{1}{R^{t+2}} c_0^{-\gamma-1} \left(-\gamma \frac{\bar{r} \phi}{R \phi + \gamma} k_0 + c_0 \right) \quad (35)$$

²⁰In this section, because FOCs with respect to consumption are considered, the labor supply (N_t) is omitted.

Since $u_{c_0} = V_{k_0}$, we have $u_{cc}\partial_{\bar{r}}c_0 = \partial_{\bar{r}}V_{k_0}$, which implies

$$\partial_{\bar{r}}c_0 = \frac{\partial_{\bar{r}}\left(\frac{\partial V}{\partial k_t}\right)}{u_{cc}} = \frac{1}{R^{t+2}}\left(\frac{\bar{r}}{R}\frac{\phi}{\phi+\gamma}k_0 - \frac{1}{\gamma}c_0\right) \quad (36)$$

which gives the expression for $b_r(k_t) = \frac{1}{R^{t+2}}\left(\frac{\bar{r}}{R}\frac{\phi}{\phi+\gamma}k_0 - \frac{1}{\gamma}c_0\right)$.

We take the derivative of the value function with respect to y_t . Applying the envelope theorem yields

$$\frac{\partial V}{\partial y_t} = \frac{\partial L}{\partial y_t} = \beta^t\left(\frac{\partial u(c_t)}{\partial y_t} + \beta\lambda_t^k(1+r_t)\right) \quad (37)$$

By deriving this expression with respect to k_0 , we find the following expression

$$\frac{\partial}{\partial k_0}\left(\frac{\partial V}{\partial y_t}\right) = \beta^t\frac{\partial k_t}{\partial k_0}\frac{\partial}{\partial k_t}\left[\frac{\partial u(c_t)}{\partial y_t} + \beta\lambda_t^k(1+r_t)\right] \quad (38)$$

Eq. 38 can be simplified as

$$\frac{\partial}{\partial k_0}\left(\frac{\partial V}{\partial y_t}\right) = \frac{1}{R^t}\left(-\gamma\frac{\bar{r}}{R}c_0^{-\gamma-1}\right) \quad (39)$$

Since $u_{c_0} = V_{k_0}$, we have $u_{cc}\partial_{\hat{y}}c_0 = \partial_{\hat{y}}V_{k_0}$, which implies

$$\partial_{\hat{y}}c_0 = \frac{\partial_{\hat{y}}\left(\frac{\partial V}{\partial k_0}\right)}{u_{cc}} = \frac{\bar{r}}{R^{t+1}} \quad (40)$$

Once we obtain Eq. 36 and Eq. 40, the Taylor expansion of \hat{c} can be expressed as

$$\hat{c}_t = \mathbb{E}_t \sum_{\tau \geq t} \frac{b_r|_{k=0}\hat{r}_\tau + b_y\hat{y}_\tau}{R^{\tau-t+1}} \quad (41)$$

where $b_r = \frac{1}{R}\left(\frac{\bar{r}}{R}k_0 - \frac{1}{\gamma}c_0\right)$ and $b_y = \bar{r}$.

For the behavioral agent expression, 41 becomes

$$\hat{c}_t = \mathbb{E}_t^{BR} \sum_{\tau \geq t} \frac{b_r|_{k=0}\hat{r}_\tau + b_y\hat{y}_\tau}{R^{\tau-t+1}} \quad (42)$$

Recall from Gabaix (2019) the term structure of attention: $\mathbb{E}_t^{BR}[\hat{r}_{t+k}] = m_r\bar{m}^k\mathbb{E}_t[\hat{r}_{t+k}]$ and $\mathbb{E}_t^{BR}[\hat{y}_{t+k}] = m_y\bar{m}^k\mathbb{E}_t[\hat{y}_{t+k}]$, where \bar{m} , m_r and m_y are general, interest rate and revenue myopia, respectively. By replacing those expressions in Eq. 42, we obtain

$$\hat{c}_t = \mathbb{E}_t \sum_{\tau \geq t} \frac{\bar{m}^{\tau-t}}{R^{\tau-t+1}} (b_r|_{k=0}m_r\hat{r}_\tau + b_y m_y\hat{y}_\tau) \quad (43)$$

Dividing Eq. 43 by \bar{c} , we find

$$\frac{\hat{c}_t}{\bar{c}} = \mathbb{E}_t \sum_{\tau \geq t} \frac{\bar{m}^{\tau-t}}{R^{\tau-t+1}} \left(\frac{b_{r|k=0}}{\bar{c}} m_r \hat{r}_\tau + b_y m_y \frac{\hat{y}_\tau}{\bar{c}} \right) \quad (44)$$

The market clearing condition is $y_t = c_t$, and thus $\frac{\hat{c}_t}{\bar{c}} = \frac{\hat{y}_t}{\bar{c}} = \tilde{y}_t$ is the output gap. Moreover, $\frac{b_{r|k=0}}{\bar{c}} = \frac{1}{\bar{c}} \frac{1}{R} \left(-\frac{1}{\gamma} c_0 \right) = -\frac{1}{\gamma R}$.

Then, Eq. 44 becomes

$$\tilde{y}_t = \mathbb{E}_t \sum_{\tau \geq t} \frac{\bar{m}^{\tau-t}}{R^{\tau-t+1}} \left(-\frac{1}{\gamma R} m_r \hat{r}_\tau + \bar{r} m_y \tilde{y}_\tau \right) \quad (45)$$

Expanding this expression yields

$$\tilde{y}_t = -\frac{1}{\gamma R^2} m_r \hat{r}_t + \frac{\bar{r}}{R} m_y \tilde{y}_t + \frac{\bar{m}}{R} \mathbb{E}_t \tilde{y}_{t+1} \quad (46)$$

which can be simplified to

$$\tilde{y}_t = M \mathbb{E}_t [\tilde{y}_{t+1}] - \sigma \hat{r}_t \quad (47)$$

where $M = \frac{\bar{m}}{R - \bar{r} m_y}$, $\sigma = \frac{m_r}{\gamma R (R - \bar{r} m_y)}$ and $R = 1/\beta$.

A.2 Phillips curve

The problem of the behavioral firm is then to maximize

$$\sum_{k=0}^{\infty} \theta^k \mathbb{E}_t^{BR} [\Lambda_{t,t+k} (P_t^* Y_{t+k|t} - \Psi_{t+k}(Y_{t+k|t}))] \quad (48)$$

subject to the sequence of demand constraints

$$Y_{t+k|t} = \left(\frac{P_t^*}{P_{t+k}} \right)^{-\varepsilon} Y_{t+k} \quad (49)$$

where $\Lambda_{t,t+k} = \beta^k (C_{t+k}/C_t)^{-\gamma} (P_{t+k}/P_t)$ is the stochastic discount factor in nominal terms, $\Psi_{t+k}(\cdot)$ is the cost function, and $Y_{t+k|t}$ denotes the output in period $t+k$ for a firm that last reset its price in period t .

The FOC of the problem is the following

$$\sum_{k=0}^{\infty} \theta^k \mathbb{E}_t^{BR} [\Lambda_{t,t+k} Y_{t+k|t} (P_t^* - \mathcal{M}\psi_{t+k|t})] = 0 \quad (50)$$

where $\mathcal{M} = \frac{\varepsilon}{\varepsilon-1}$ is the desired or frictionless markup.

By dividing Eq. 50 by P_{t-1} and defining $\Pi_{t,t+k} = \frac{P_{t+k}}{P_t}$ and $MC_{t+k/t} = \frac{\psi_{t+k|t}}{P_{t+k}}$, we obtain the following

$$\sum_{k=0}^{\infty} \theta^k \mathbb{E}_t^{BR} \left[\Lambda_{t,t+k} Y_{t+k|t} \left(\frac{P_t^*}{P_{t-1}} - \mathcal{M} MC_{t+k/t} \Pi_{t-1,t+k} \right) \right] = 0 \quad (51)$$

We define the steady state of $\Lambda_{t,t+k}$ as β^k , $Y_{t+k|t}$ as Y , $\frac{P_t^*}{P_{t-1}}$ as 1, $MC_{t+k/t}$ as $\frac{1}{\mathcal{M}}$, and $\Pi_{t-1,t+k}$ as 1. These defined steady states allow us to expand the FOC (Eq. 51) as follows

$$\sum_{k=0}^{\infty} (\beta\theta)^k \mathbb{E}_t^{BR} [p_t^* - p_{t-1} - (\widehat{mc}_{t+k/t} + p_{t+k} - p_{t-1})] = 0 \quad (52)$$

with small letters denoting the logarithm of capital letters $p_t = \ln P_t$ and hat indicating the deviation with respect to the steady state $\widehat{mc}_{t+k/t} = mc_{t+k/t} - mc$, where $mc_{t+k/t} = \ln MC_{t+k/t}$, and $mc = -\mu$, where $\mu = \ln \mathcal{M}$.

By simplifying Eq. 52 we obtain

$$p_t^* - p_{t-1} = (1 - \beta\theta) \sum_{k=0}^{\infty} (\beta\theta)^k \mathbb{E}_t^{BR} [\widehat{mc}_{t+k/t} + p_{t+k} - p_{t-1}] \quad (53)$$

By rearranging the terms of Eq. 53, we obtain

$$p_t^* = \mu + (1 - \beta\theta) \sum_{k=0}^{\infty} (\beta\theta)^k \mathbb{E}_t^{BR} [mc_{t+k/t} + p_{t+k}] \quad (54)$$

The (log) marginal cost can be expressed as

$$mc_{t+k|t} = mc_{t+k} - \frac{\alpha\varepsilon}{1-\alpha} (p_t^* - p_{t+k}) \quad (55)$$

We replace Eq. 55 in Eq. 53 and find

$$p_t^* - p_{t-1} = (1 - \beta\theta) \sum_{k=0}^{\infty} (\beta\theta)^k \mathbb{E}_t^{BR} \left[\widehat{mc}_{t+k} - \frac{\alpha\varepsilon}{1-\alpha} (p_t^* - p_{t+k}) + p_{t+k} - p_{t-1} \right] \quad (56)$$

Rearranging terms leads to the following expression

$$p_t^* - p_{t-1} = (1 - \beta\theta) \sum_{k=0}^{\infty} (\beta\theta)^k \mathbb{E}_t^{BR} [\Theta \widehat{mc}_{t+k} + p_{t+k} - p_{t-1}] \quad (57)$$

where $\Theta = \frac{1-\alpha}{1-\alpha+\alpha\varepsilon}$.

Eq. 57 can be expressed as

$$p_t^* - p_{t-1} = (1 - \beta\theta) \Theta \sum_{k=0}^{\infty} (\beta\theta)^k \mathbb{E}_t^{BR} [\widehat{mc}_{t+k}] + \sum_{k=0}^{\infty} (\beta\theta)^k \mathbb{E}_t^{BR} [\pi_{t+k}] \quad (58)$$

We recall the term structure of expectations from Gabaix (2019): $\mathbb{E}_t^{BR} [\pi_{t+k}] = m_\pi^f \bar{m}^k \mathbb{E}_t [\pi_{t+k}]$ and $\mathbb{E}_t^{BR} [\widehat{mc}_{t+k}] = m_x^f \bar{m}^k \mathbb{E}_t [\widehat{mc}_{t+k}]$, where \bar{m} is the general myopia to the evolution of the economy's state, m_π^f is the myopia to prices, and m_x^f is the myopia related to output. Hence, Eq. 58 can be rewritten as

$$p_t^* - p_{t-1} = (1 - \beta\theta) \Theta \sum_{k=0}^{\infty} (\beta\theta)^k m_x^f \bar{m}^k \mathbb{E}_t [\widehat{mc}_{t+k}] + \sum_{k=0}^{\infty} (\beta\theta)^k m_\pi^f \bar{m}^k \mathbb{E}_t [\pi_{t+k}] \quad (59)$$

By writing this equation as a difference equation, we find

$$p_t^* - p_{t-1} = \beta\theta \bar{m} \mathbb{E}_t [p_{t+1}^* - p_t] + (1 - \beta\theta) \Theta m_x^f \widehat{mc}_t + m_\pi^f \pi_t \quad (60)$$

We combine Eq. 60 with $\pi_t = (1 - \theta)(p_t^* - p_{t-1})$ and obtain

$$\pi_t = \frac{\beta\theta \bar{m}}{1 - (1 - \theta) m_\pi^f} \mathbb{E}_t [\pi_{t+1}] + \frac{(1 - \theta) (1 - \beta\theta) \Theta m_x^f \widehat{mc}_t}{1 - (1 - \theta) m_\pi^f} \quad (61)$$

We express the real marginal cost, mc_t , as a function of the output gap, \tilde{y}_t . Notice that the real marginal cost is defined in terms of the real wage and marginal productivity of labor

$$mc_t = w_t - mpn_t \quad (62)$$

Using the facts that the real wage equals the marginal rate of substitution between consumption and labor and that the marginal productivity can be derived from Eq. 11, expression Eq. 62 can be written as

$$mc_t = (\gamma y_t + \phi n_t) - (y_t - n_t) - \ln(1 - \alpha) \quad (63)$$

We use the production function Eq. 11 to eliminate n_t from Eq. 63, and we obtain

$$mc_t = \left(\gamma + \frac{\phi + \alpha}{1 - \alpha} \right) y_t - \frac{1 + \phi}{1 - \alpha} a_t - \ln(1 - \alpha) \quad (64)$$

Writing Eq. 64 in the flexible price economy yields

$$mc = \left(\gamma + \frac{\phi + \alpha}{1 - \alpha} \right) y_t^n - \frac{1 + \phi}{1 - \alpha} a_t - \ln(1 - \alpha) \quad (65)$$

where y_t^n is the natural output. Finally, by subtracting Eq. 65 from Eq. 64, we

obtain

$$\widehat{m}c_t = \left(\gamma + \frac{\phi + \alpha}{1 - \alpha} \right) (y_t - y_t^n) = \left(\gamma + \frac{\phi + \alpha}{1 - \alpha} \right) \tilde{y}_t \quad (66)$$

Finally, by replacing Eq. 66 in the price setting Eq. 61, we obtain

$$\pi_t = \frac{\beta \theta \bar{m}}{1 - (1 - \theta) m_\pi^f} \mathbb{E}_t [\pi_{t+1}] + \frac{(1 - \theta)(1 - \beta \theta) \Theta m_x^f}{1 - (1 - \theta) m_\pi^f} \left(\gamma + \frac{\phi + \alpha}{1 - \alpha} \right) \tilde{y}_t \quad (67)$$

The resulting behavioral Phillips curve is

$$\pi_t = \beta M^f \mathbb{E}_t [\pi_{t+1}] + \kappa \tilde{y}_t \quad (68)$$

where $M^f = \frac{\theta \bar{m}}{1 - (1 - \theta) m_\pi^f}$ and $\kappa = \frac{(1 - \theta)(1 - \beta \theta) \Theta m_x^f}{1 - (1 - \theta) m_\pi^f} \left(\gamma + \frac{\phi + \alpha}{1 - \alpha} \right)$.

Note that if we consider the rational case, where $m_x^f = m_\pi^f = \bar{m} = 1$, we end up with the usual Phillips curve as in Galí (2015).

A.3 Natural output

The marginal cost of a firm is defined as

$$\mu_t = -w_t - mpn_t \quad (69)$$

where mpn_t is the marginal productivity of labor. Recall that the marginal rate of substitution between labor and consumption equals the real wage, which can be expressed as

$$-\frac{U_{n,t}}{U_{c,t}} = \frac{W_t}{P_t} \quad (70)$$

Taking logs, we obtain $w_t = \phi n_t + \gamma c_t$.

For the marginal productivity of labor in logs, we have

$$mpn_t = a - \alpha n_t + \ln(1 - \alpha) \quad (71)$$

and because the production function takes the form $y_t = a_t + (1 - \alpha) n_t$, we can express the marginal cost formula in terms of output and a technological factor as

$$\mu_t = - \left(\gamma + \frac{\phi + \alpha}{1 - \alpha} \right) y_t - \frac{1 + \phi}{1 - \alpha} a_t - \ln(1 - \alpha) \quad (72)$$

By expressing this formula in the flexible price economy, we obtain

$$\mu = - \left(\gamma + \frac{\phi + \alpha}{1 - \alpha} \right) y_t^n - \frac{1 + \phi}{1 - \alpha} a_t - \ln(1 - \alpha) \quad (73)$$

where $\mu = \ln\left(\frac{\varepsilon}{\varepsilon-1}\right)$ is the marginal cost prevailing under flexible prices and y_t^n is the natural output.

By solving for y_t^n , we obtain the expression for natural output as

$$y_t^n = \frac{1 + \phi}{\phi + \alpha + \gamma(1 - \alpha)} a_t + \frac{(1 - \alpha)(-\mu + \ln(1 - \alpha))}{\phi + \alpha + \gamma(1 - \alpha)} \quad (74)$$

A.4 Efficient interest rate

The IS curve Eq. 75 is written as

$$\hat{y}_t = M\mathbb{E}_t[\hat{y}_{t+1}] - \sigma(i_t - \mathbb{E}_t[\pi_{t+1}] - r_t^n) \quad (75)$$

Note that the definitions of the output gap, \hat{y}_t , and the relevant output gap, x_t , are

$$\hat{y}_t = y_t - y_t^n \quad (76)$$

$$x_t = y_t - y_t^e \quad (77)$$

where y_t^n is the natural output and y_t^e is the efficient output.

By employing those definitions, we can write the IS curve Eq. 19 as

$$y_t - y_t^n = M\mathbb{E}_t[y_{t+1} - y_{t+1}^n] - \sigma(i_t - \mathbb{E}_t[\pi_{t+1}] - r_t^n) \quad (78)$$

which is equivalent to

$$y_t - y_t^e + y_t^e - y_t^n = M\mathbb{E}_t[y_{t+1} - y_{t+1}^e + y_{t+1}^e - y_{t+1}^n] - \sigma(i_t - \mathbb{E}_t[\pi_{t+1}] - r_t^n) \quad (79)$$

The welfare-relevant output gap is

$$x_t + y_t^e - y_t^n = M\mathbb{E}_t[x_{t+1} + y_{t+1}^e - y_{t+1}^n] - \sigma(i_t - \mathbb{E}_t[\pi_{t+1}] - r_t^n) \quad (80)$$

which leads us to the following expression

$$x_t = M\mathbb{E}_t[x_{t+1}] + M\mathbb{E}_t[y_{t+1}^e - y_{t+1}^n] - (y_t^e - y_t^n) - \sigma(i_t - \mathbb{E}_t[\pi_{t+1}] - r_t^n) \quad (81)$$

Hence, we obtain

$$x_t = M\mathbb{E}_t[x_{t+1}] - \sigma(i_t - \mathbb{E}_t[\pi_{t+1}] - r_t^e) \quad (82)$$

where

$$r_t^e = r_t^n + \frac{1}{\sigma} (M\mathbb{E}_t[y_{t+1}^e - y_{t+1}^n] - (y_t^e - y_t^n)) \quad (83)$$

By taking Eq. 83 in deviation from its flexible price economy counterpart, we

obtain an expression for the efficient interest rate in deviation form such as

$$r_t^e - r_t^n = \left[r_t^n + \frac{1}{\sigma} (M\mathbb{E}_t [y_{t+1}^e - y_{t+1}^n] - (y_t^e - y_t^n)) \right] - \left[r_t^n + \frac{1}{\sigma} (M\mathbb{E}_t [y_{t+1}^n - y_{t+1}^n] - (y_t^n - y_t^n)) \right] \quad (84)$$

Considering the notation $\hat{v} = v - v^n$, Eq. 84 can be simplified to

$$\hat{r}_t^e = \frac{1}{\sigma} (M\mathbb{E}_t [\hat{y}_{t+1}^e] - \hat{y}_t^e) \quad (85)$$

A.5 Welfare loss

The Taylor expansion of the utility function U_t defined in Eq. 1 is the following

$$U_t - U = U_c c \left(\frac{c_t - c}{c} \right) + \frac{1}{2} U_{cc} c^2 \left(\frac{c_t - c}{c} \right)^2 + U_n N \left(\frac{N_t - N}{N} \right) + \frac{1}{2} U_{nn} N^2 \left(\frac{N_t - N}{N} \right)^2 + \Theta(Z^3) \quad (86)$$

where $\Theta(Z^3)$ represents the terms up to the power of 3 and null cross variables derivatives due to the separability of our utility function.

To further develop the Eq. 86, we use the fact that $U_{cc} = -\gamma \frac{1}{c} U_c$ and $U_{nn} = -\phi \frac{1}{N} U_n$. Moreover, note that for any variable z_t , we have $\frac{z_t - z}{z} = \hat{z}_t + \frac{1}{2} \hat{z}_t^2$.

Taking into account all of this, Eq. 86 becomes

$$U_t - U = U_c c \left(\hat{c}_t + \frac{1 - \gamma}{2} \hat{c}_t^2 \right) + U_n N \left(\hat{n}_t + \frac{1 + \phi}{2} \hat{n}_t^2 \right) + \Theta(Z^3) \quad (87)$$

We express \hat{n}_t in terms of \tilde{y}_t (remember that \tilde{y}_t is our notation for the output gap from Section 2.1). Using $Y_t(i) = \left(\frac{P_t(i)}{P_t} \right)^{-\epsilon} Y_t$ and $P_t = \left(\int_0^1 P_t(i)^{1-\epsilon} di \right)^{\frac{1}{1-\epsilon}}$, we have

$$\begin{aligned} N_t &= \int_0^1 N_t(i) di \\ &= \int_0^1 \left(\frac{Y_t(i)}{A_t} \right)^{\frac{1}{1-\alpha}} di \\ &= \left(\frac{Y_t}{A_t} \right)^{\frac{1}{1-\alpha}} \int_0^1 \left(\frac{P_t(i)}{P_t} \right)^{-\frac{\epsilon}{1-\alpha}} di \end{aligned}$$

In terms of log deviations, this expression can be written as

$$(1 - \alpha) \hat{n}_t = \tilde{y}_t - a_t + d_t$$

where $d_t = (1 - \alpha) \ln \int_0^1 \left(\frac{P_t(i)}{P_t} \right)^{-\frac{\epsilon}{1-\alpha}} di$. It follows from Lemma 1 (Galí (2015), chapter 4) that

$$d_t = \frac{\epsilon}{2\Theta} \text{var}_i \{p_t(i)\}$$

Returning to our Taylor expansion Eq. 87 and using the fact that $\hat{c}_t = \tilde{y}_t$, we obtain

$$U_t - U = U_{cC} \left(\tilde{y}_t + \frac{1-\gamma}{2} \tilde{y}_t^2 \right) + \frac{U_n N}{1-\alpha} \left(\tilde{y}_t + \frac{\epsilon}{2\Theta} \text{var}_i \{p_t(i)\} + \frac{1+\phi}{2(1-\alpha)} (\tilde{y}_t - a_t)^2 \right) \quad (88)$$

The efficiency of the steady state implies

$$-\frac{U_n}{U_c} = MPN = (1-\alpha) \frac{Y}{N}$$

By combining the previous two equations we find

$$\frac{U_t - U}{U_{cC}} = \tilde{y}_t + \frac{1-\gamma}{2} \tilde{y}_t^2 - \left(\tilde{y}_t + \frac{\epsilon}{2\Theta} \text{var}_i \{p_t(i)\} + \frac{1+\phi}{2(1-\alpha)} (\tilde{y}_t - a_t)^2 \right) \quad (89)$$

As in Galí (2015), we can consider that the product of Φ with second-order terms is null under the assumption of small distortions. We obtain

$$\begin{aligned} \frac{U_t - U}{U_{cC}} &= -\frac{1}{2} \left[\frac{\epsilon}{\Theta} \text{var}_i \{p_t(i)\} - (1-\gamma) \tilde{y}_t^2 + \frac{1+\phi}{1-\alpha} (\tilde{y}_t - a_t)^2 \right] \\ &= -\frac{1}{2} \left[\frac{\epsilon}{\Theta} \text{var}_i \{p_t(i)\} + \left(\gamma + \frac{\phi + \alpha}{1-\alpha} \right) \tilde{y}_t^2 - 2 \left(\frac{1+\phi}{1-\alpha} \right) \tilde{y}_t a_t \right] \quad (90) \end{aligned}$$

Using the fact that $\hat{y}_t^e = \frac{1+\phi}{\gamma(1-\alpha)+\phi+\alpha} a_t$, we obtain

$$\frac{U_t - U}{U_{cC}} = -\frac{1}{2} \left[\frac{\epsilon}{\Theta} \text{var}_i \{p_t(i)\} + \left(\gamma + \frac{\phi + \alpha}{1-\alpha} \right) (\tilde{y}_t - \hat{y}_t^e)^2 \right]$$

The welfare loss is expressed as a fraction of the steady-state consumption

$$\begin{aligned} \mathbb{W} &= -\mathbb{E}_0 \sum_{t=0}^{\infty} \beta^t \left(\frac{U_t - U}{U_{cC}} \right) \\ &= -\mathbb{E}_0 \sum_{t=0}^{\infty} \beta^t \left[-\frac{1}{2} \left(\frac{\epsilon}{\Theta} \text{var}_i \{p_t(i)\} + \left(\gamma + \frac{\phi + \alpha}{1-\alpha} \right) (\tilde{y}_t - \hat{y}_t^e)^2 \right) \right] \quad (91) \end{aligned}$$

Assuming that $x_t = y_t - y_t^e = \tilde{y}_t - \hat{y}_t^e$ and by applying Lemma 2 (Galí (2015)),

chapter 4), we find the welfare loss expression

$$\mathbb{W} = -\mathbb{E}_0 \sum_{t=0}^{\infty} \beta^t \left[-\frac{1}{2} \left(\frac{\epsilon}{\Theta} \frac{\theta}{(1-\beta\theta)(1-\theta)} \pi_t^2 + \left(\gamma + \frac{\phi + \alpha}{1-\alpha} \right) x_t^2 \right) \right] \quad (92)$$

B Robustness check

This section presents our results under the alternative model and myopia calibrations.

B.1 Model calibrations

Table 7 presents the different model calibrations considered in the following robustness analysis.

Calibration name	β	γ	ϕ	ϵ	α	θ
Galí (2008)	0.99	1	1	6	1/3	0.66
Relative risk aversion	0.99	2	1	6	1/3	0.66
Frisch elasticity	0.99	1	5	6	1/3	0.66
Constant return to scale	0.99	1	1	6	0	0.66
Sticky prices	0.99	1	1	6	1/3	3/4
Time preferences	0.996	1	1	6	1/3	0.66
Demand elasticity	0.99	1	1	9	1/3	0.66
Galí (2015)	0.996	2	5	9	1/3	3/4

Table 7: Calibration of the model parameters used for the robustness checks.

Fig. 4 to Fig. 7 present the impulse response of inflation, output, interest rate and price level under commitment, respectively, over the different calibrations presented in Table 7. Fig. 8 to Fig. 11 present the impulse response of inflation, output, interest rate and price level under commitment, respectively, over the different calibrations presented in Table 7.

Impulse responses functions for optimal simple rules under each calibration are available upon request. Welfare heatmaps for commitment and discretion under the different model calibrations (Table 7) are presented in Table 8. Welfare heatmaps of optimal simple rules under different model calibrations are available upon request.

The impulse response functions lead to similar conclusions as in Sections 4.2 and 5.2, whatever the model calibration chosen.

Recall from section 2.2 the discussion about the effect of constant returns to scale; it is worth noting that when $\alpha \neq 0$, the trade-off between inflation and output worsens, and the central bank acts aggressively in order to accommodate the




Figure 4: Impulse response functions of inflation following a 1% cost-push shock under commitment for each model and myopia calibration.

cost-push shock as it is clear from the Figures below when comparing the baseline calibration to the constant returns to scale calibration $\alpha = 0$.

Table 8 reveals that under different model calibrations, myopia does not necessarily increase welfare losses. Interestingly, our previous results hold. Increasing the Frisch elasticity or decreasing the constant return to scale leads to lower welfare losses whatever the type of myopia. Under discretion and optimal simple rules, the welfare-improving abilities of the general myopia are clear and robust. This result is not clear under commitment for such myopia levels (85%), but extreme myopia values demonstrate the robustness of this result (Appendix B.2).




Figure 5: Impulse response functions of output following a 1% cost-push shock under commitment for each model and myopia calibration.




Figure 6: Impulse response functions of interest rate following a 1% cost-push shock under commitment for each model and myopia calibration.




Figure 7: Impulse response functions of price level following a 1% cost-push shock under commitment for each model and myopia calibration.




Figure 8: Impulse response functions of inflation following a 1% cost-push shock under discretion for each model and myopia calibration.




Figure 9: Impulse response functions of output following a 1% cost-push shock under discretion for each model and myopia calibration.




Figure 10: Impulse response functions of interest rate following a 1% cost-push shock under discretion for each model and myopia calibration.




Figure 11: Impulse response functions of price level following a 1% cost-push shock under discretion for each model and myopia calibration.

Myopia	Rational	0.2809	0.2235	0.1126	0.1248	0.4667	0.2832	0.2624	0.1741
	Interest rate	0.2809	0.2235	0.1126	0.1248	0.4667	0.2832	0.2624	0.1741
	Output-gap	0.3599	0.2892	0.1492	0.1649	0.5830	0.3627	0.3372	0.2274
	Inflation	0.3171	0.2533	0.1286	0.1424	0.5039	0.3199	0.2966	0.1901
	Revenue	0.2809	0.2235	0.1126	0.1248	0.4667	0.2832	0.2624	0.1741
	General	0.2834	0.2257	0.1136	0.1260	0.4672	0.2861	0.2648	0.1760
	Full	0.3962	0.3223	0.1699	0.1873	0.6043	0.4001	0.3727	0.2478
Myopia	Rational	0.5102	0.3740	0.1528	0.1740	1.0109	0.5212	0.4649	0.2697
	Interest rate	0.5102	0.3740	0.1528	0.1740	1.0109	0.5212	0.4649	0.2697
	Output-gap	0.7148	0.5308	0.2189	0.2494	1.3426	0.7315	0.6543	0.3862
	Inflation	0.5324	0.4005	0.1713	0.1942	0.9864	0.5432	0.4892	0.2868
	Revenue	0.5102	0.3740	0.1528	0.1740	1.0109	0.5212	0.4649	0.2697
	General	0.4149	0.3165	0.1403	0.1583	0.7347	0.4222	0.3828	0.2362
	Full	0.5625	0.4484	0.2155	0.2412	0.8907	0.5721	0.5264	0.3407
		Gali (2008)	Relative risk aversion	Frisch elasticity	Constant return to scale	Sticky prices	Time preference	Demand elasticity	Gali (2015)

Table 8: Welfare losses under commitment (top) and discretion (bottom) for each calibration.

B.2 Myopia calibrations

The different myopia cases considered in this section are presented in Table 9.

	Models							
	No myopia	Myopia						
	Rational	Interest rate	Output gap	Inflation	Revenue	General	Full	Extreme
m_r	1	0.2	1	1	1	1	0.2	0.01
m_x^f	1	1	0.2	1	1	1	0.2	0.01
m_π^f	1	1	1	0.2	1	1	0.2	0.01
m_y	1	1	1	1	0.2	1	0.2	0.01
\bar{m}	1	1	1	1	1	0.2	0.2	0.01

Table 9: Calibration of the myopia parameters used for the simulations.

Table 9 presents more pronounced myopic agents with approximately 80% myopia and an extreme case with an almost fully myopic agent (99%). The impulse response functions resulting from the calibration presented in Table 9 are presented in the case of commitment (Fig. 12) and discretion (Fig. 13). The optimal simple rule cases are available upon request.




Figure 12: Impulse response functions of inflation, price level, output and interest rate following a 1% cost-push shock under commitment for each model calibration (Table 9).

Table 10 presents the welfare losses under the standard calibration Galí (2015) for commitment and discretion. Here again the results for the optimal simple rule cases are available upon request. The results under the different calibrations presented in Table 9 are also available upon request.




Figure 13: Impulse response functions of inflation, price level, output and interest rate following a 1% cost-push shock under discretion for each model calibration (Table 9).

	Myopia						
	Interest rate	Output gap	Inflation	Revenue	General	Full	Extreme
Commitment	0.174	1.446	0.257	0.174	0.143	0.372	0.302
Discretion	0.270	3.357	0.348	0.270	0.145	0.372	0.302

Table 10: Welfare losses under commitment and discretion for each myopia calibration.

Table 10 shows that the welfare losses under discretion are always higher than under commitment, except under full and extreme myopia. Interestingly, the general myopia case leads to the best welfare losses under commitment and discretion, confirming our result that myopia can also improve welfare losses.

From these robustness analyses, one can conclude that there exists a general myopia level that improves the welfare losses whatever the chosen commitment, discretion or optimal simple rule regime.

Published papers (in English)

R. Melnick and Y. Golan – Measurement of Business Fluctuations in Israel.	91.01
M. Sokoler – Seigniorage and Real Rates of Return in a Banking Economy.	91.03
E.K. Offenbacher – Tax Smoothing and Tests of Ricardian Equivalence Israel 1961-1988.	91.04
M. Beenstock, Y. Lavi and S. Ribon – The Supply and Demand for Exports in Israel.	91.07
R. Ablin – The Current Recession and Steps Required for Sustained Recovery and Growth.	91.08
M. Beenstock – Business Sector Production in the Short and Long Run in Israel: A Cointegrated Analysis.	91.10
A. Marom – The Black-Market Dollar Premium: The Case of Israel.	91.13
A. Bar-Ilan and A. Levy – Endogenous and Exogenous Restrictions on Search for Employment.	91.14
M. Beentstock and S. Ribon – The Market for Labor in Israel.	91.15
O. Bar Efrat – Interest Rate Determination and Liberalization of International Capital Movement: Israel 1973-1990.	92.02
Z. Sussman and D. Zakai – Wage Gaps between Senior and Junior Physicians and Crises in Public Health in Israel, 1974-1990.	92.03
O. Leviathan – The Impact of Real Shocks on Fiscal Redistribution and Their Long-Term Aftermath.	92.05
A. Bregman, M. Fuss and H. Regev – The Production and Cost Structure of the Israeli Industry: Evidence from Individual Firm Data.	92.06
M. Beenstock, Y. Lavi and A. Offenbacher – A Macroeconometric Model for Israel 1962-1990: A Market Equilibrium Approach to Aggregate Demand and Supply.	92.07
R. Melnick – Financial Services, Cointegration and the Demand for Money in Israel.	92.09
R. Melnick – Forecasting Short-Run Business Fluctuations in Israel.	92.12
K. Flug, N. Kasir and G. Ofer – The Absorption of Soviet Immigrants in to the Labor Market from 1990 Onwards: Aspects of Occupational Substitution and Retention.	92.13

B. Eden – How to Subsidize Education and Achieve Voluntary Integration: An Analysis of Voucher Systems.	93.01
A. Arnon and D. Gottlieb – An Economic Analysis of the Palestinian Economy: The West Bank and Gaza, 1968-1991.	93.07
K. Flug and N. Kasir – The Absorption in the Labor Market of Immigrants from the CIS - the Short Run.	93.09
R. Ablin – Exchange Rate Systems, Incomes Policy and Stabilization Some Short and Long-Run Considerations.	94.01
B. Eden – The Adjustment of Prices to Monetary Shocks When Trade is Uncertain and Sequential.	94.02
K. Flug, Z. Hercowitz and A. Levi – A Small -Open-Economy Analysis of Migration.	94.04
R. Melnick and E. Yashiv – The Macroeconomic Effects of Financial Innovation: The Case of Israel.	94.05
A. Blass – Are Israeli Stock Prices Too High?	94.09
A. Arnon and J. Weinblatt – The Potential for Trade Between Israel the Palestinians, and Jordan.	94.10
B. Eden – Inflation and Price Dispersion: An Analysis of Micro Data.	94.13
B. Eden – Time Rigidities in The Adjustment of Prices to Monetary Shocks: An Analysis of Micro Data.	94.16
O. Yosha – Privatizing Multi-Product Banks.	94.17
B. Eden – Optimal Fiscal and Monetary Policy in a Baumol-Tobin Model.	95.01
B. Bar-Nathan, M. Beenstock and Y. Haitovsky – An Econometric Model of The Israeli Housing Market.	95.02
A. Arnon and A. Spivak – A Seigniorage Perspective on the Introduction of a Palestinian Currency.	95.04
M. Bruno and R. Melnick – High Inflation Dynamics: Integrating Short-Run Accommodation and Long-Run Steady-States.	95.06
M. Strawczynski – Capital Accumulation in a Bequest Economy.	95.08
A. Arnon and A. Spivak – Monetary Integration Between the Israeli, Jordanian and Palestinian Economies.	95.11

A. Blass and R.S. Grossman – A Harmful Guarantee? The 1983 Israel Bank Shares Crisis Revisited.	96.03
Z. Sussman and D. Zakai – The Decentralization of Collective Bargaining and Changes in the Compensation Structure in Israeli’s Public Sector.	96.04
M. Strawczynski – Precautionary Savings and The Demand for Annuities.	96.05
Y. Lavi and A. Spivak – The Impact of Pension Schemes on Saving in Israel: Empirical Analysis.	96.09
M. Strawczynski – Social Insurance and The Optimum Piecewise Linear Income Tax.	96.10
M. Dahan and M. Strawczynski – The Optimal Non-Linear Income Tax.	97.02
H. Ber, Y. Yafeh and O. Yosha – Conflict of Interest in Universal Banking: Evidence from the Post-Issue Performance of IPO Firms.	97.05
A. Blass, Y. Yafeh and O. Yosha – Corporate Governance in an Emerging Market: The Case of Israel.	97.08
N. Leviathan and R. Melnick – Inflation and Disinflation by Steps in Israel.	98.01
A. Blass and Y. Yafeh – Vagabond Shoes Longing to Stray - Why Israeli Firms List in New York - Causes and Implications.	98.02
G. Bufman and L. Leiderman – Monetary Policy and Inflation in Israel.	98.04
Z. Hercowitz and M. Strawczynski – On the Cyclical Bias in Government Spending.	98.06
A. Brender – The Effect of Fiscal Performance on Local Government Election Results in Israel: 1989-1998.	99.04
S. Ribon and O. Yosha – Financial Liberalization and Competition in Banking: An Empirical Investigation.	99.05
L. Leiderman and H. Bar-Or – Monetary Policy Rules and Transmission Mechanisms Under Inflation Targeting in Israel.	2000.01
Z. Hercowitz and M. Strawczynski – Public-Debt / Output Guidelines: The Case of Israel.	2000.03
Y. Menashe and Y. Mealem – Measuring the Output Gap and its Influence on The Import Surplus.	2000.04

J. Djivre and S. Ribon – Inflation, Unemployment, the Exchange Rate and Monetary Policy in Israel 1990-1999: A SVAR Approach.	2000.06
J. Djivre and S. Ribon – Monetary Policy, the Output Gap and Inflation: A Closer Look at the Monetary Policy Transmission Mechanism in Israel 1989-1999.	2000.09
J. Braude – Age Structure and the Real Exchange Rate.	2000.10
Z. Sussman and D. Zakai – From Promoting the Worthy to Promoting All: The Public Sector in Israel 1975-1999.	2000.11
H. Ber, A. Blass and O. Yosha – Monetary Transmission in an Open Economy: The Differential Impact on Exporting and Non-Exporting Firms.	2001.01
N. Leviathan – Tight Money and Central Bank Intervention - A selective analytical survey.	2001.03
Y. Lavi and N. Sussman – The Determination of Real Wages in the Long Run and its Changes in the Short Run - Evidence from Israel: 1968-1998.	2001.04
J. Braude – Generational Conflict? Some Cross-Country Evidence.	2001.06
Z. Hercowitz and M. Strawczynski – Cyclical Ratcheting in Government Spending: Evidence from the OECD.	2001.09
D. Romanov and N. Zussman – On the Dark Side of Welfare: Estimation of Welfare Recipients Labor Supply and Fraud.	2001.12
A. Blass O. Peled and Y. Yafeh – The Determinants of Israel’s Cost of Capital: Globalization, Reforms and Politics.	2002.03
N. Leviathan – The Money-Injection Function of the Bank of Israel and the Inflation Process.	2002.04
Y. Menashe – Investment under Productivity Uncertainty.	2002.07
T. Suchoy and A. Friedman – The NAIRU in Israel: An Unobserved Components Approach.	2002.08
R. Frish and N. Klein – Rules versus Discretion - A Disinflation Case.	2002.09
S. Ribon – Is it labor, technology or monetary policy? The Israeli economy 1989-2002.	2003.02
A. Marom, Y. Menashe and T. Suchoy – The State-of-The-Economy Index and the probability of Recession: The Markov Regime-Switching Model.	2003.05
N. Leviathan and R. Frish – Public Debt in a Long-Term Discretionary Model.	2003.07

D. Romanov – The Real Exchange Rate and the Balassa-Samuelson Hypothesis: An Appraisal of Israel’s Case Since 1986.	2003.09
R. Frish – Restricting capital outflow - the political economy perspective.	2003.10
H. Ber and Y. Yafeh – Venture Capital Funds and Post-IPO Performance in Booms and Busts: Evidence from Israeli IPO’s in the US in the 1990s.	2003.12
N. Klein – Reputation and Indexation in an Inflation Targeting Framework.	2003.13
N. Leviathan – Fiscal Dominance and Monetary Dominance in the Israeli Monetary Experience.	2003.17
A. Blass and S. Ribon – What Determines a Firm's Debt Composition - An Empirical Investigation.	2004.04
R. Sharabany – Business Failures and Macroeconomic Risk Factors.	2004.06
N. Klein – Collective Bargaining and Its Effect on the Central Bank Conservatism: Theory and Some Evidence.	2004.07
J. Braude and Y. Menashe – Does the Capital Intensity of Structural Change Matter for Growth?	2004.10
S. Ribon – A New Phillips Curve for Israel.	2004.11
A. Barnea and J. Djivre – Changes in Monetary and Exchange Rate Policies and the Transmission Mechanism in Israel, 1989.IV – 2002.I.	2004.13
M. Dahan and M. Strawczynski – The Optimal Asymptotic Income Tax Rate.	2004.15
N. Klein – Long-Term Contracts as a Strategic Device.	2004.16
D. Romanov – The corporation as a tax shelter: evidence from recent Israeli tax changes.	2004.17
T. Suchoy – Does the Israeli Yield Spread Contain Leading Signals? A Trial of Dynamic Ordered Probit.	2004.18
A. Brender – Ethnic Segregation and the Quality of Local Government in the Minorities Localities: Local Tax Collection in the Israeli-Arab Municipalities as a Case Study.	2005.01
A. Zussman and N. Zussman – Targeted Killings: Evaluating the Effectiveness of a Counterterrorism Policy.	2005.02
N. Leviathan and R. Frish – Interest on reserves and inflation.	2005.03

A. Brender and A. Drazen – Political Budget Cycles in New versus Established Democracies.	2005.04
Z. Hercowitz and M. Strawczynski – Government Spending Adjustment: The OECD Since the 1990s.	2005.09
Y. Menashe – Is the Firm-Level Relationship between Uncertainty and Irreversible Investment Non- Linear?	2005.12
A. Friedman – Wage Distribution and Economic Growth.	2005.13
E. Barnea and N. Leviathan – Nominal Anchor: Economic and Statistical Aspects.	2006.01
A. Zussman, N. Zussman and M. Ørregaard Nielsen – Asset Market Perspectives on the Israeli-Palestinian Conflict.	2006.02
N. Presman and A. Arnon – Commuting patterns in Israel 1991-2004.	2006.04
G. Navon and I. Tojerow – The Effects of Rent-sharing On the Gender Wage Gap in the Israeli Manufacturing Sector.	2006.05
S. Abo Zaid – The Trade–Growth Relationship in Israel Revisited: Evidence from Annual Data, 1960-2004.	2006.11
M. Strawczynski and J. Zeira – Cyclicity of Fiscal Policy in Israel.	2007.04
A. Friedman – A Cross-Country Comparison of the Minimum Wage.	2007.05
K. Flug and M. Strawczynski – Persistent Growth Episodes and Macroeconomic Policy Performance in Israel.	2007.08
S. Miaari, A. Zussman and N. Zussman – Ethnic Conflict and Job Separations.	2008.04
Y. Mazar – Testing Self-Selection in Transitions between the Public Sector and the Business Sector.	2008.07
A. Brender and L. Gallo – The Response of Voluntary and Involuntary Female Part-Time Workers to Changes in Labor-Market Conditions.	2008.08
A. Friedman – Taxation and Wage Subsidies in a Search-Equilibrium Labor Market.	2008.10
N. Zussman and S. Tsur – The Effect of Students' Socioeconomic Background on Their Achievements in Matriculation Examinations.	2008.11
R. Frish and N. Zussman – The Causal Effect of Parents' Childhood Environment and Education on Their Children's Education.	2009.02

E. Argov – The Choice of a Foreign Price Measure in a Bayesian Estimated New-Keynesian Model for Israel.	2009.04
G. Navon – Human Capital Spillovers in the Workplace: Labor Diversity and Productivity.	2009.05
T. Suhoy – Query Indices and a 2008 Downturn: Israeli Data.	2009.06
J. Djivre and Y. Menashe – Testing for Constant Returns to Scale and Perfect Competition in the Israeli Economy, 1980–2006.	2009.07
S. Ribon – Core Inflation Indices for Israel	2009.08
A. Brender – Distributive Effects of Israel's Pension System.	2009.10
R. Frish and G. Navon – The Effect of Israel’s Encouragement of Capital Investments in Industry Law on Product, Employment, and Investment: An Empirical Analysis of Micro Data.	2009.12
E. Toledano, R. Frish, N. Zussman, and D. Gottlieb – The Effect of Child Allowances on Fertility.	2009.13
D. Nathan – An Upgrade of the Models Used to Forecast the Distribution of the Exchange Rate.	2010.01
A. Sorezcky – Real Effects of Financial Signals and Surprises.	2010.02
B. Schreiber – Decomposition of the ILS/USD Exchange Rate into Global and Local Components.	2010.03
E. Azoulay and S. Ribon – A Basic Structural VAR of Monetary Policy in Israel Using Monthly Frequency Data.	2010.04
S. Tsur and N. Zussman – The Contribution of Vocational High School Studies to Educational Achievement and Success in the Labor Market.	2010.05
Y. Menashe and Y. Lavi – The Long- and Short-Term Factors Affecting Investment in Israel's Business-Sector, 1968-2008.	2010.06
Y. Mazar – The Effect of Fiscal Policy and its Components on GDP in Israel.	2010.07
P. Dovman – Business Cycles in Israel and Macroeconomic Crises - Their Duration and Severity.	2010.08
T. Suhoy – Monthly Assessments of Private Consumption.	2010.09
A. Sorezcky – Did the Bank of Israel Influence the Exchange Rate?	2010.10

Y. Djivre and Y. Yakhin – A Constrained Dynamic Model for Macroeconomic Projection in Israel.	2010.11
Y. Mazar and N. Michelson – The Wage Differentials between Men and Women in Public Administration in Israel – An Analysis Based on Cross-Sectional and Panel Data.	2010.12
A. Friedman and Z. Hercowitz – A Real Model of the Israeli Economy.	2010.13
M. Graham – CEO Compensation at Publicly Traded Companies.	2010.14
E. Azoulay and R. Shahrabani – The Level of Leverage in Quoted Companies and Its Relation to Various Economic Factors.	2010.15
G. Dafnai and J. Sidi – Nowcasting Israel GDP Using High Frequency Macroeconomic Disaggregates.	2010.16
E. Toledano, N. Zussman, R. Frish and D. Gottlieb – Family Income and Birth Weight.	2010.17
N. Blass, S. Tsur and N. Zussman – The Allocation of Teachers' Working Hours in Primary Education, 2001–2009.	2010.18
T. Krief – A Nowcasting Model for GDP and its Components.	2011.01
W. Nagar – Persistent Undershooting of the Inflation Target During Disinflation in Israel: Inflation Avoidance Preferences or a Hidden Target?	2011.02
R. Stein – Estimating the Expected Natural Interest Rate Using Affine Term-Structure Models: The Case of Israel.	2011.03
R. Sharabani and Y. Menashe – The Hotel Market in Israel.	2011.04
A. Brender – First Year of the Mandatory Pension Arrangement: Compliance with the Arrangement as an Indication of its Potential Implications for Labor Supply.	2011.05
P. Dovman, S. Ribon and Y. Yakhin – The Housing Market in Israel 2008-2010: Are Housing Prices a “Bubble”?	2011.06
N. Steinberg and Y. Porath – Chasing Their Tails: Inflow Momentum and Yield Chasing among Provident Fund Investors in Israel.	2011.07
L. Gallo – Export and Productivity – Evidence From Israel.	2011.08
I. Gamrasni – The Effect of the 2006 Market Makers Reform on the Liquidity of Local-Currency Unindexed Israeli Government Bonds in the Secondary Market.	2011.09
H. Etkes – The Impact of Employment in Israel on the Palestinian Labor Force.	2011.11

S. Ribon – The Effect of Monetary Policy on Inflation: A Factor Augmented VAR Approach using disaggregated data.	2011.12
A. Sasi-Brodesky – Assessing Default Risk of Israeli Companies Using a Structural Model.	2011.13
Y. Mazar and O. Peled – The Minimum Wage, Wage Distribution and the Gender Wage Gap in Israel 1990–2009.	2012.01
N. Michelson – The Effect of Personal Contracts in Public Administration in Israel on Length of Service.	2012.02
S. Miaari, A. Zussman and N. Zussman – Employment Restrictions and Political Violence in the Israeli-Palestinian Conflict.	2012.04
E. Yashiv and N. K. (Kaliner) – Arab Women in the Israeli Labor Market: Characteristics and Policy Proposals.	2012.05
E. Argov, E. Barnea, A. Binyamini, E. Borenstein, D. Elkayam and I. Rozenshtrom – MOISE: A DSGE Model for the Israeli Economy.	2012.06
E. Argov, A. Binyamini, E. Borenstein and I. Rozenshtrom – Ex-Post Evaluation of Monetary Policy.	2012.07
G. Yeshurun – A Long School Day and Mothers' Labor Supply.	2012.08
Y. Mazar and M. Haran – Fiscal Policy and the Current Account.	2012.09
E. Toledano and N. Zussman – Terror and Birth Weight.	2012.10
A. Binyamini and T. Larom – Encouraging Participation in a Labor Market with Search and Matching Frictions.	2012.11
E. Shachar – The Effect of Childcare Cost on the Labor Supply of Mothers with Young Children.	2012.12
G. Navon and D. Chernichovsky – Private Expenditure on Healthcare, Income Distribution, and Poverty in Israel.	2012.13
Z. Naor – Heterogeneous Discount Factor, Education Subsidy, and Inequality.	2012.14
H. Zalkinder – Measuring Stress and Risks to the Financial System in Israel on a Radar Chart.	2012.15
Y. Saadon and M. Graham – A Composite Index for Tracking Financial Markets in Israel.	2013.01

A. Binyamini – Labor Market Frictions and Optimal Monetary Policy.	2013.02
E. Borenstein and D. Elkayam – The equity premium in a small open economy, and an application to Israel.	2013.03
D. Elkayam and A. Ilek – Estimating the NAIRU for Israel, 1992–2011.	2013.04
Y. Yakhin and N. Presman – A Flow-Accounting Model of the Labor Market: An Application to Israel.	2013.05
M. Kahn and S. Ribon – The Effect of Home and Rent Prices on Private Consumption in Israel - A Micro Data Analysis.	2013.06
S. Ribon and D. Sayag – Price Setting Behavior in Israel – An Empirical Analysis Using Microdata.	2013.07
D. Orfaig (Flikier) – The Weighting of the Bank of Israel CPI Forecast - a Unified Model.	2013.08
O. Sade, R. Stein and Z. Wiener – Israeli Treasury Auction Reform.	2013.09
D. Elkayam and A. Ilek – Estimating the NAIRU using both the Phillips and the Beveridge curves.	2013.10
A. Ilek and G. Segal – Optimal monetary policy under heterogeneous beliefs of the central bank and the public.	2014.01
A. Brender and M. Strawczynski – Government Support for Young Families in Israel.	2014.02
Y. Mazar – The Development of Wages in the Public Sector and their Correlation with Wages in the Private Sector.	2014.03
H. Etkes – Do Monthly Labor Force Surveys Affect Interviewees’ Labor Market Behavior? Evidence from Israel’s Transition from Quarterly to Monthly Surveys.	2014.06
N. Blass, S. Tsur and N. Zussman – Segregation of students in primary and middle schools.	2014.07
A. Brender and E. Politzer – The Effect of Legislated Tax Changes on Tax Revenues in Israel.	2014.08
D. Sayag and N. Zussman – The Distribution of Rental Assistance Between Tenants and Landlords: The Case of Students in Central Jerusalem.	2015.01
A. Brender and S. Ribon – The Effect of Fiscal and Monetary Policies and the Global Economy on Real Yields of Israel Government Bonds.	2015.02

I. Caspi – Testing for a Housing Bubble at the National and Regional Level: The Case of Israel.	2015.05
R. Stein – The Effects of Taxation of Capital Gains on the Pricing of Financial Assets.	2015.06
E. Barnea and Y. Menashe – Banks Strategies and Credit Spreads as Leading Indicators for the Real Business Cycles Fluctuations.	2015.07
R. Frish – Currency Crises and Real Exchange Rate Depreciation.	2016.01
V. Lavy and E. Sand – On the Origins of Gender Gaps in Human Capital: Short- and Long-Term Consequences of Teachers’ Biases.	2016.02
R. Frish – The Real Exchange Rate in the Long Term.	2016.03
A. Mantzura and B. Schreiber – Carry trade attractiveness: A time-varying currency risk premium approach.	2016.04
N. Blass, S. Tsur, and N. Zussman – Local-Authority Funding of Primary School Instruction hours and Its Effect on Affirmative Action in the State (Jewish, Non-Religious) Education System.	2016.05
I. Caspi and M. Graham – Testing for Bubbles in Stock Markets with Irregular Dividend Distribution.	2016.06
E. Borenstein, and D. Elkayam – Financial Distress and Unconventional Monetary Policy in Financially Open Economies.	2016.09
S. Afek and N. Steinberg – The Foreign Exposure of Public Companies Traded on the Tel Aviv Stock Exchange.	2016.10
R. Stein – Review of the Reference Rate in Israel: Telbor and Makam Markets.	2016.12
N. Sussman and O. Zohar – Has Inflation Targeting Become Less Credible? Oil Prices, Global Aggregate Demand and Inflation Expectations during the Global Financial Crisis.	2016.13
E. Demalach, D. Genesove, A. Zussman and N. Zussman – The Effect of Proximity to Cellular Sites on Housing Prices in Israel.	2016.14
E. Argov – The Development of Education in Israel and its Contribution to Long-Term Growth Discussion Paper.	2016.15
S. Tsur – Liquidity Constraints and Human Capital: The Impact of Welfare Policy on Arab Families in Israel.	2017.01

G. Segal – Interest Rate in the Objective Function of the Central Bank and Monetary Policy Design.	2017.02
N. Tzur-Ilan – The Effect of Credit Constraints on Housing Choices: The Case of LTV limit.	2017.03
A. Barak – The private consumption function in Israel	2017.04
S. Ribon – Why the Bank of Israel Intervenes in the Foreign Exchange Market, and What Happens to the Exchange Rate.	2017.04
E. Chen, I. Gavious and N. Steinberg – Dividends from Unrealized Earnings and Default Risk.	2017.05
A. Ilek and I. Rozenshtrom – The Term Premium in a Small Open Economy: A Micro-Founded Approach.	2017.06
A. Sasi-Brodesky – Recovery Rates in the Israeli Corporate Bond Market 2008–2015.	2017.07
D. Orfaig – A Structural VAR Model for Estimating the Link between Monetary Policy and Home Prices in Israel.	2017.09
M. Haran Rosen and O. Sade – Does Financial Regulation Unintentionally Ignore Less Privileged Populations? The Investigation of a Regulatory Fintech Advancement, Objective and Subjective Financial Literacy.	2017.10
E. Demalach and N. Zussman – The Effect of Vocational Education on Short- and Long-Term Outcomes of Students: Evidence from the Arab Education System in Israel.	2017.11
S. Igdalov, R. Frish and N. Zussman – The Wage Response to a Reduction in Income Tax Rates: The 2003–2009 Tax Reform in Israel.	2017.14
Y. Mazar – Differences in Skill Levels of Educated Workers between the Public and Private Sectors, the Return to Skills and the Connection between them: Evidence from the PIAAC Surveys.	2018.01
M. Graham-Rozen and N. Michelson – To Accept or Not to Accept? Considerations in Providing Credit Insurance.	2018.03
I. Caspi, A. Friedman, and S. Ribon – The Immediate Impact and Persistent Effect of FX Purchases on the Exchange Rate.	2018.04
D. Elkayam and G. Segal – Estimated Natural Rate of Interest in an Open Economy: The Case of Israel.	2018.05
Y. Mazar and Y. Reingewertz – The Effect of Child Allowances on Labor Supply Evidence from Israel.	2018.07

N. B. Itzhak – The Effect of Terrorism on Housing Rental Prices: Evidence from Jerusalem.	2018.08
M. Rosenboim, Y. Saadon, B. Z. Schreiber – “Much Ado about Nothing”? The Effect of Print Media Tone on Stock Indices.	2018.10
K. Kosenko and N. Michelson – It Takes More than Two to Tango: Understanding the Dynamics behind Multiple Bank Lending and its Implications.	2018.11
N. Tzur-Ilan – LTV Limits and Borrower Risk.	2018.12
T. Suhoy and Y. Sofer – Getting to Work in Israel: Locality and Individual Effects.	2019.02
A. Barak – The Effect of Public Transit on Employment in Israel's Arab Society	2019.03
E. Argov and S. Tsur – A Long-Run Growth Model for Israel.	2019.04
E. Argov and S. Tsur – Conditional Convergence and Future TFP Growth in Israel.	2019.05
O. Zohar – Boom-Bust Cycles of Learning, Investment and Disagreement.	2019.06
J. Benchimol and L. Bounader – Optimal Monetary Policy under Bounded Rationality.	2019.07